

1 050483

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,346-00.00

E/2 SW SE, SEC. 31, T 33 S, R 11 W/EX  
660 feet from S section line  
2210/1650 <sup>keep</sup> feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042  
Operator: Edmiston Oil Co., Inc.  
Name & Address: 1260 Kansas State Bank Building  
Wichita, KS 67202

Lease Name Newkirk Well # 1  
County Barber 152.75  
Well Total Depth 4700 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 286

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:00 pm Day: 25 Month: March Year: 19 85

Plugging proposal received from Neil Peddicord  
(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4699' PRTD 4689' Perfs at 4617-4627'

1st plug pump 1 sack hulls and 25 sx cement to bottom

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 125 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30 pm Day: 25 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 25 sx cement to bottom.

2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION

APR 04 1985

Maximum pressure 700 psi and shut in 500 psi

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Recovered 3500' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Sun. additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~xxxxxxx~~) observe this plugging.

DATE 4-9-85  
INV. NO. 2526

Signed Richard W. Lacy (TECHNICIAN)