

1 040454

8-23

00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,920-A
C SE NW, SEC. 22, T 33 S, R 12 WXE
3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6581

Lease Name Harbaugh Well # F-1

Operator: Bison Energy Corporation
Name & Address P.O. Box 782317
Wichita, KS 67278

County Barber 160.84
Well Total Depth 4949 feet

Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11:30 a.m. Day: 23 Month: 8 Year: 19 90

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4712' w/150 sx cement, PBD 4610', Perfs at 4540-62'
1st plug sand back to 4490' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

STATE CORPORATION COMMISSION

AUG 29 1990

Plugging Proposal Received by Mike Spain
Wichita, Kansas (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 p.m. Day: 23 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4490' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

AUG 29 1990

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3390' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

DATE: 8-30-90

INV. NO. 29174