

1 050522

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,036-00-00

C SW \_\_\_\_\_, SEC. 23, T 33 S, R 12 (W/R)  
1320 feet from S section line  
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5601

Lease Name Vincent Well # 1

Operator: Associated Petroleum Cons., Inc.  
Name & Address One Main Place, Suite 600

County Barber 169.00 (Simpson)

Wichita, KS 67202-1399

Well Total Depth 5200 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A x \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Heartland Drilling, Inc. License Number 5867

Address One Main Place, Suite 600, Wichita, KS 67202

Company to plug at: Hour: 8:00 am Day: 17 Month: May Year: 19 85

Plugging proposal received from Mike Tharpa

(company name) Heartland (phone) 316-265-9723

Elevation 1500

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 660

1st plug at 690' with 50 sx cement

2nd plug at 300' with 40 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10:15 am Day: 17 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 690' with 50 sx cement, 2nd plug at 300' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

RECEIVED

STATE CORPORATION COMMISSION

MAY 28 1985

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton # 082900

(if additional description is necessary, use BACK of this form.)

INVOICED

(xxx did not) observe this plugging.

DATE 5-29-85

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 8280

5-17