

1-6

To: 120202
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,450-0000
SW NW NW, SEC. 25, T 19 S, R 16 (W) E

TECHNICIAN'S PLUGGING REPORT

Operator License # 8541

4290 feet from S section line

4950 feet from E section line

Operator: Petex, Inc.

Lease Name Tammen Well # 1

Name & Address 1111 South Glenstone, Suite 1-104

County Rush 122.23

Springfield, MO 65804

Well Total Depth 3761 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1028

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Bldg., Wichita, KS 67202

Company to plug at: Hour: 1:30 a.m. Day: 6 Month: 1 Year: 19 89

Plugging proposal received from Pat Waggoner

(company name) Red Tiger Drilling Company (phone) 316-263-1201

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1970' Anhydrite 1021-46'

1st plug at 3670' with 40 sx cement, 2nd plug at 1065' with 50 sx cement,

3rd plug at 500' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 6 a.m. Day: 6 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 3760' with 40 sx cement,

2nd plug at 1065' with 50 sx cement,

3rd plug at 500' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (If desired, observe this plugging.)

DATE 1-12-89

WV. No. 23646

Signed Dan Goodrow (TECHNICIAN)

RECEIVED
JAN 10 1989
CONSERVATION DIVISION
WICHITA, KANSAS

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... December 26, 1988

API Number 15-165-21,450-3000

OPERATOR: License # 8541
Name... Petex, Inc
Address 1111 S. Glenstone, #1-104
City/State Springfield, MO 65804
Contact Person... Larry Childress
Phone... (417) 887-6289

SW NW NW 25 19S 16
4290 Twp S. Rg. 16
4950 Ft. from South Line of Section
Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 990.330 feet
County Rush

CONTRACTOR: License #
Name Lobo Drilling Company
City/State Great Bend, KS

Lease Name Tammen Well # 1
Ground surface elevation 1970 feet MSL

Well Drilled For:
X Oil Storage Infield Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Domestic well within 330 feet yes X no
Municipal well within one mile yes X no

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Depth to bottom of fresh water 180
Depth to bottom of usable water 330

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 12/16/88 Signature of Operator or Agent Larry Childress Title President

Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 1000

Conductor pipe required n/a
Projected Total Depth 3800 feet
Formation Arbuckle

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 350 feet per Alt. 1
This Authorization Expires 6-19-89 Approved By KCM 12-19-88

EFFECTIVE DATE: 12-21-88
More on 12-27-88 set @ 1000

SW NW NW 25 19S 16W
Sec. Twp S. Rg. West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep... Arbuckle or formation with... 35 feet of 60/40 pozmix
2nd plug @ ft. deep... Anhydrite or formation with... 50 feet of...!!
3rd plug @ ft. deep... 350' or formation with... 50 feet of...!!
4th plug @ ft. deep... 40' or formation with... 10 feet of...!!
5th plug @ ft. deep... or formation with... feet of...

(2) Rathole to surface minus 5 feet (b) Mousehole to surface minus 5 feet

PUSHER Pat Wagener
TD 3761' FORMATION Arb.
SURFACE PIPE 8 5/8" @ 1000'
ANHYDRITE 1021'-46' ELEVATION 1970
STARTING TIME & DATE 4:00 AM
COMPLETION TIME & DATE 6:00 AM 1-6-89
1st PLUG @ 3670 FT. W/ 40 SX
2nd PLUG @ 1065 FT. W/ 50 SX
3rd PLUG @ 500 FT. W/ 40 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE-HOLE CIRCULATED W/ SX
WATER WELL-PLUGGED W/ SX
CEMENT COMPANY Allied 6940 67
TECHNICIAN Dan Goodrow
Did not see
STATE OF KANSAS
JAN 10 1989
1-10-89
CONSERVATION
WELL