

1 060041

6-18

CORPORATION COMMISSION  
Office Bldg. - PLUGGING SECTION  
at, Room 2078  
ta. KS 67202

API NUMBER 15- Spud date 3/12/66 15/35-36/88

C NW SW, SEC. 18, T 20 S, R 22 W/EX  
1980 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 9615

Lease Name Stairrett A Well # 1

Operator: Joe Gerstner Oil Company

County Ness 140.89

Name & Address 302 E. Sycamore

Well Total Depth 4335 feet

Ness City, KS 67560

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 230

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Hembree Well Service License Number 32066

Address P.O. Box 458, Ness City, KS 67560

Company to plug at: Hour: 11 a.m. Day: 18 Month: 6 Year: 19 97

Plugging proposal received from Pat Gerstner

(company name) Joe Gerstner Oil Co. (phone) 918-798-2893

Work: 5 1/2" at 4325' w/175 sx cement, Open hole

1st plug pump 25 sx cement on bottom,

2nd plug circulate cement from 900-0'.

Check backside.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 p.m. Day: 18 Month: 6 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 4130' with 25 sx cement and 100 lbs. hulls through tubing,

2nd plug at 750-0' with 80 sx cement and 200 lbs. hulls,

3rd plug pulled tubing and topped off with 20 sx cement.

Hooked onto backside and pressured to 500 psi, held.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

Signed Michael J. Miller  
(TECHNICIAN)

DATE JUL 03 1997

INV. NO. 48472

6-18

RECEIVED  
KANSAS CORP COM  
197 JUN 20 PM 1:40  
6-26-97