

1 070783

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3762Operator: Alpine Petroleum, Inc.

Name &

Address 2nd Floor, Southwestern Bell Bldg.Box 66El Dorado, KS 67042Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ O&A ☐Other well as hereinafter indicated ☐Plugging Contractor Plains, Inc. License Number 4072Address P.O. Box 346, Ness City, KS 67560Company to plug at: Hour: 10:25 a.m. Day: 30 Month: 1 Year: 19 90Plugging proposal received from Clint Base(company name) Plains, Inc. (phone) 913-798-3995were: 4 1/2" at 4357' PBTD 4340' Openhole Elevation 2236' GL1st plug perms to 1000' with Econolite,2nd plug perforate casing at 800', squeeze 50 sx cement and fill casing,3rd plug pump 100 sx cement down backside.Plugging Proposal Received by DAV Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐Operations Completed: Hour: 2:30 p.m. Day: 30 Month: 1 Year: 19 90ACTUAL PLUGGING REPORT 1st plug pumped 75 sx Econolite with 300 lbs. hulls down 4 1/2",
displaced cement with water to 1000',2nd plug perforated 4 1/2" at 800', pumped 100 sx 60/40 Pozmix 6% gel down 4 1/2" displacing
50 sx through perms,3rd plug pumped 100 sx 60/40 Pozmix 6% gel down 4 1/2" X 8 5/8" annulus.Remarks: Used Econolite and 60/40 Pozmix 6% gel by Halliburton. No casing recovery division
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-12-90INV. NO. 27410Signed Dan Goodrow

(TECHNICIAN)

GREAT GUNS

R/A Log

FILING NO.		COMPANY PALOMINO PETROLEUM					
		WELL GROSS NO. 1 15135 30144 0001					
		FIELD					
		COUNTY NESS	STATE KANSAS				
LOCATION:		OTHER SERVICES					
SEC 13 TWP 20s RGE 22w							
PERMANENT DATUM GROUND LEVEL		ELEV 2236'	ELEV KB 2246'				
LOG MEASURED FROM KELLY BUSHING 10 FT. ABOVE PERM. DATUM		D.F. 2243'					
DRILLING MEASURED FROM KELLY BUSHING		G.L. 2236'					
DATE	12-11-70						
RUN NO.	ONE						
TYPE LOG	GAMMA						
DEPTH-DRILLER	4173'						
DEPTH-LOGGER	4173'						
BOTTOM LOGGED INTERVAL	4173'						
TOP LOGGED INTERVAL	3500'						
TYPE FLUID IN HOLE	WATER & OIL						
SALINITY, PPM CL							
DENSITY							
LEVEL							
MAX. REC. TEMP. DEG F							
OPERATING RIG TIME	ONE HOUR	RECEIVED					
RECORDED BY	ROBBEN	STATE CORPORATION COMMISSION					
WITNESSED BY	MR. WATCHOUS	JAN 10 1990					
RUN	BORE-HOLE RECORD			CASING RECORD			
NO.	BIT	FROM	TO	SIZE	WGT	FROM	TO
				4 1/2	9 1/2	000	4358'