

1 050730

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,419-0000

C SW NE , SEC. 14 , T 20 S, R 22 (W/E)

TECHNICIAN'S PLUGGING REPORT

3300 feet from (S) section line

1980 feet from (E) section line

Operator License # 5316

Lease Name Maier Well # 2

Operator: Falcon Exploration, Inc.

County Ness

Name & Address 1531 Kansas State Bank Building

Well Total Depth 4396 142.87 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 636

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Falcon Exploration, Inc. License Number 5316

Address 1531 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 9:00 am Day: 18 Month: December Year: 19 85

Plugging proposal received from Zack Lewis

(company name) Falcon (phone) 316-262-1378

were: 5 1/2" at 4371' Open hole 4376-4396

1st plug sand back to 4325' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 11 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:00 am Day: 19 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4325' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 11 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 400 psi and shut in 200 psi

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. (If additional description is necessary, use BACK of this form.)

INVOICED
DATE DEC 27 1985
INV. NO. 11736
12-19

RECEIVED
STATE CORPORATION COMMISSION
12-27-85
DEC 27 1985
Signed Richard W. Lacy (TECHNICIAN)

FEB 5 1986 MAR 27 1986
CONSERVATION DIVISION