

To: 1 070042
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE SE NW , SEC. 20 , T 30 S, R 14 W/8
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,093-0000
3400 feet from S section line
3060 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4456
Operator: F M P Operating Co.
Name & Address: P. O. Box 15640
Lakewood, CO 80215

Lease Name Simpson Well # 1-20
County Barber
Well Total Depth 4700 Arbuckle 152.75 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 915'

Abandoned Oil Well Gas Well Input Well SWD Well D&A x
Other well as hereinafter indicated

Plugging Contractor Allen Drilling Company License Number 5418
Address P. O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 4:00 am Day: 29 Month: October Year: 19 85

Plugging proposal received from Gary Christopher

(company name) Allen Drilling (phone) 316-793-5681

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1840 GL
Anhydrite 620'(top)

- 1st plug at 950' with 50 sx cement
- 2nd plug at 360' with 40 sx cement solid bridge
- 3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement
- 5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:00 am Day: 29 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 950' with 50 sx cement, 2nd plug at 360' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE NOV 4 1985

INV. NO. 10877

RECEIVED
OCT 30 1985
CONSERVATION DIVISION
Wichita, Kansas

Signed Dan Goodson (TECHNICIAN)

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 10 21 85 month day year

API Number 15-007-22,093-0000

OPERATOR: License # 4456 Name F.M.P. Operating Co. Address Box 15640 City/State/Zip Lakewood, CO 80215 Contact Person Steve Hoppe Phone 303-987-9512

NE..SE..NW... Sec..20. Twp..30. S, Rg....14. X West 3400 Ft. from South Line of Section 3060 Ft. from East Line of Section (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5418 Name Allen Drilling Co. City/State Box 1389 Great Bend, KS 67530

Nearest lease or unit boundary line 420 feet County Barber Lease Name Simpson Well # 1-20 Ground surface elevation 1840 feet MSL Domestic well within 330 feet yes X no Municipal well within one mile yes X no Surface pipe by Alternate: 1 X 2 Depth to bottom of fresh water 150 Depth to bottom of usable water 200 Surface pipe planned to be set 300 Projected Total Depth 4650 feet Formation Arbuckle-Simpson

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 10/17/85 Signature of Operator or Agent Title As Agent

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt. 2 This Authorization Expires 4-17-86 Approved By 10-17-85

move in 10-18-85 at least 300' SP

50 SX base Any

30' below SP. 50 SX if 300' set

wiper plug, 40' - 0' - 10 SX.

circ. 10 SX in Rat

60/40 6% ✓

Arbuckle TD - 4700'

8 5/8 950 w/ 50 SX ✓ w/ 40 SX ✓

360 40 w/ SB + 10 SX

15 SX Rathole BT Titan

6:00 AM

10:29 AM

Job Janky 600

Elw 1840 GL

RECEIVED STATE CORPORATION COMMISSION

NOV 1 1985 11-1-85 CONSERVATION DIVISION