

1 050785

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,127-~~0000~~  
S/2 S/2 NW, SEC. 16, T 30 S, R 14 (W)

TECHNICIAN'S PLUGGING REPORT

Operator License # 5533

2970 feet from S section line  
3960 feet from E section line

Operator: Arrowhead Petroleum, Inc.  
Name & Address: P. O. Box 8287- Munger Station  
Wichita, KS 67208

Lease Name Stannard Well # 1  
County Barber 154.05  
Well Total Depth 4740 Arbuckle feet

Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 326

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Big Springs Drilling, Inc. License Number 5381  
Address Box 8287 - Munger Station, Wichita, KS 67208

Company to plug at: Hour: 9:00 pm Day: 21 Month: March Year: 19 86

Plugging proposal received from Darrel Krier  
(company name) Big Springs (phone) 316-681-1732

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 690' Elevation 1951'

1st plug at 700' with 50 sx cement

2nd plug at 330' with 50 sx cement  
solid bridge

3rd plug bulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11:15 pm Day: 21 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 700' with 50 sx cement, 2nd plug at 330' with 50 sx cement, 3rd & 4th plugs - solid bridge - bulls - plug at 40' -- cement to surface with 10 sx cement. 5th plug to circulate rat hole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 31 1986  
3-31-86  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(If additional description is necessary, use BACK of this form.)

I (check) did not observe this plugging.

Signed Richard W. Lacey  
(TECHNICIAN)

DATE APR 1 1986

INV. NO. 13193

3-21

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date March 8, 1986 month day year

API Number 15- 007-22,127-0000

OPERATOR: License # 5533
Name Arrowhead Petroleum, Inc.
Address Box 8287 - Munger Station
City/State/Zip Wichita, Kansas 67208
Contact Person Wm. Todd Seymour
Phone (316) 681-3921

S/2 S/2 NW Sec. 16 Twp. 30 S, Rg. 14W East
2970 Ft. from South Line of Section
3960 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5381
Name Big Springs Drilling, Inc.
City/State Wichita, Kansas 67208

Nearest lease or unit boundary line 330' feet
County Barber
Lease Name Stannard Well # 1
Ground surface elevation 1951 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water 150'
Depth to bottom of usable water 200'
Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 8 5/8" @ 300'
Conductor pipe required
Projected Total Depth 4750' feet
Formation Arbuckle

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

If OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq. plus eventually plugging hole to KCC specifications.
Date 2-28-86 Signature of Operator or Agent Title Geologist

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per API 104
This Authorization Expires 9-5-86 Approved By 3-5-86

Set 300' of 8 5/8 on 3/12/86

S/2 S/2 NW Sec. 16 Twp. 30 S, Rg. 14W East

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug depth, feet depth with, and sxs of. Includes handwritten entries for 1st plug @ 700', 2nd plug @ 330', 3rd plug @ 40', 4th plug @ RH, 5th plug @ 15', and (2) Rathole with 15' sxs.

PUSHER Darrel Krier
TD 4740 FORMATION Arbuckle
SURFACE PIPE 8 5/8 @ 326
ANHYDRITE 690 ELEVATION 1951
STARTING TIME & DATE 9:00pm 3/2/86
COMPLETION TIME & DATE 11:15pm 3/2/86
1st PLUG @ 200 FT. W/ 50 SX
2nd PLUG @ 330 FT. W/ 50 SX
3rd PLUG @ 40 FT. W/ 50 SX
4th PLUG @ FT. W/ SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX

CEMENT COMPANY Halliburton
TECHNICIAN

RECEIVED STATE CORPORATION COMMISSION

MAR 31 1986
3-31-86
CONSERVATION DIVISION
Wichita, Kansas