

To: 1 041303  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-007-22463-0000  
150' W C  
NE, NE, NW, SW SEC. 13, T 30 S, R 14 W/4  
RECEIVED  
KANSAS 2310  
4-20-78 840  
1998 APR 20 AM 11:51

TECHNICIAN'S PLUGGING REPORT

Operator License / 5506  
Operator: Woolsey Petroleum Corp.  
Name:  
Address: P.O. Box 168  
Medicine Lodge, KS. 67104

Lease Name Gillespie Well # 1  
County Barber 157.14  
Well Total Depth 4835 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4" feet 216

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address 107 W. Fowler, P.O. Box 187, Medicine Lodge, Ks. 67104

Company to plug at: Hour: 2:00 P.m Day: 9 Month: 4 Year: 1998

Plugging proposal received from Alan Vratil

(company name) Clarke Corporation (phone) 316-886-5665

Work: 5 1/2" casing @ 4808 w/ 150 sx. cement, PBT D @ 4770, Perfs @ 4688-4694'

1<sup>st</sup> plug set cast Iron Bridge Plug @ 4640' + dump 2 sx. cement on top of CIBP through bailer,

2<sup>nd</sup> plug Pump down 10 3/4" surface pipe w/ 300# hulls, 10 sx. gel, 50 sx. cmt., 10 sx. gel, 100#

hulls, 10 3/4" wiper plug + 125 sx. cmt.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:45 P.m Day: 9 Month: 4 Year: 1998

ACTUAL PLUGGING REPORT 1<sup>st</sup> plug set C.I.B.P. @ 4640' + dumped 2 sx. cmt. on top of CIBP

through bailer,

2<sup>nd</sup> plug Pumped down 10 3/4" surface pipe w/ 300# hulls, 10 sx. gel, 50 sx. cmt.,

10 sx. gel, 100# hulls + 125 sx. cmt.

Max. PSI = 400# SIP = 200#

Remarks: Used 60/40 doz mix 6 gel by Allied. Recovered 2350' of 5 1/2" casing.  
(Additional description is necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging.  
DATE 4-21-98

INV. NO. 50378

Signed Stephen J. Pfeifer (TECHNICIAN)