

To: 1 040733 1-21
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-22,344-008 54R
NW NW NW, SEC. 11, T 30 S, R 14 W ~~XX~~

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056
Operator: F.G. Holl Company
Name &
Address P.O. Box 780167
Wichita, KS 67278-0167

4950 feet from S section line
4950 feet from E section line
Lease Name Johnson Well # 1-11
County Barber 152.42
Well Total Depth 4690 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 13 3/8 feet 218

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 8:45 a.m. Day: 21 Month: 1 Year: 19 93
Plugging proposal received from Kenny Gates
(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 4688' w/225 sx cement, PBSD 4652, Perfs at 3812-15'
1st plug sand back to 3770' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 175 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 9:45 a.m. Day: 21 Month: 1 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3675' and dumped 4 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 13 3/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls and 175 sx cement.
Maximum pressure 500 psi and shut in 475 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3013' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE 2-4-93

WV# 27301

Signed Stephen J. Pfeiffer
(TECHNICIAN)

RECEIVED
CORPORATION COMMISSION
6-9-93
CONSERVATION DIVISION
WICHITA, KANSAS