

1
010155

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,141-0000

NW SE NE, SEC. 10, T 30 S, R 14 W/E
3630 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5673

Lease Name Johnston Well # 1-A

Operator: W. L. Kirkman, Inc.
Name & Address: 9440 Boston, Box 782290
Wichita, KS 67218-2290

County Barber 152.33
Well Total Depth 4687 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 250'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829

Address P.O. Box 18611, Wichita, KS 67218-2290

Company to plug at: Hour: 5:00pm Day: 26 Month: July Year: 19 86

Plugging proposal received from Scott Mason

(company name) Aldebaran (phone) (316) 685-5372

- were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1898'
- 1st plug at 50' below ar buckle with 50 sx cement Anhydrite 900'
- 2nd plug at Anhydrite with 50 sx cement
- 3rd plug at 30' below surface casing with 40 sx cement
- 4th plug at 40' with 10 sx cement
- 5th plug to circulate rat hole with 15 sx cement
- 6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Jack L. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:15 pm Day: 26 Month: July Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 4687' with 40 sx cement, 2nd plug at 900' with 50 sx cement, 3rd plug at 290' with 40 sx cement, 4th plug at 40' with 15 sx cement, 5th plug to circulate the rat hole with 10 sx cement, 6th plug to circulate the mouse hole with 10 sx cement. Water supply well plugged with 10 sx cement.

RECEIVED

Remarks: Used 60/40 Poz with 6% gel by Halliburton. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-30-86

JUL 30 1986

Signed Jack L. Luthi (TECHNICIAN)

INV. NO. 14564

7-30-86