

STATE CORPORATION COMMISSION OF KANSAS  
OIL & GAS CONSERVATION DIVISION  
WELL COMPLETION FORM  
ACD-1 WELL HISTORY  
DESCRIPTION OF WELL AND LEASE

ORIGINAL

API NO. 15- 007-22599 0000

County Barber County, Kansas

NW - NW - Sec. 31 Twp. 33 Rge. 15 ~~XX~~ <sup>E</sup> <sub>W</sub>

Operator: License # 5050

Name: Hummion Corporation

Address 950 N. Tyler

City/State/Zip Wichita, KS 66212-3240

Purchaser: None

Operator Contact Person: Kent Roberts

Phone (316) 773-2300

Contractor: Name: Duke Drilling Co., Inc.

License: 5929

Wellsite Geologist: Arden Ratzlaff

Designate Type of Completion  
 New Well  Re-Entry  Workover

Oil  SWD  SLOW  Temp. Abd.  
 Gas  ENHR  SIGW  
 Dry  Other (Core, WSW, Expl., Cathodic, etc)

If Workover: KCC

Operator: SPD 6 1999

Well Name: CONFIDENTIAL

Comp. Date 08-16-99 Old Total Depth 08-27-99

Deepening  Re-perf.  Conv. to Inj/SWD  
 Plug Back  Docket No. PBTD  
 Commingled  Docket No.   
 Dual Completion  Docket No.   
 Other (SWD or Inj?)  Docket No.

08-16-99 08-27-99 08-28-99  
Spud Date Date Reached TD Completion Date

410 Feet from S/W (circle one) Line of Section

660 Feet from E/W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:  
NE, SE, NW or SW (circle one)

Lease Name Reed Well # 1

Field Name Wildcat

Producing Formation none

Elevation: Ground 1692 KB 1703

Total Depth 5470' PBTD 5550'

Amount of Surface Pipe Set and Cemented at 909 Feet

Multiple Stage Cementing Collar Used?  Yes  No

If yes, show depth set  Feet

If Alternate II completion, cement circulated from

feet depth to  w/  sx cmt.

Drilling Fluid Management Plan RAA, 9-27-99 U.C.  
(Data must be collected from the Reserve Pit)

Chloride content  ppm Fluid volume  bbls

Dewatering method used evaporation

Location of fluid disposal if hauled offsite: RELEASED

Operator Name MAR 28 2001

Lease Name CONFIDENTIAL License No.

Quarter CONFIDENTIAL S Rng.  E/W

County  Docket No.

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature Kent Roberts

Title Lease Operations Manager Date 9/15/99

Subscribed and sworn to before me this 15<sup>th</sup> day of September, 19 99.

Notary Public Joyce Cochran

Date Commission Expires 4-10-2003

K.C.C. OFFICE USE ONLY  
 Letter of Confidentiality Attached  
 Wireline Log Received  
 Geologist Report Received  
  
Distribution  
 KCC  SWD/Rep  NGPA  
 KGS  Plug  Other  
(Specify)

STATE OF KANSAS  
NOTARY PUBLIC  
JOYCE COCHRAN  
My Appt. Exp. 4-10-2003

Operator Name Hummon Corporation Lease Name Reed Well # 1

Sec. 31 Twp. 33 Rge. 15  East County Barber County, Kansas

West

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken  Yes  No  
 (Attach Additional Sheets.)

Samples Sent to Geological Survey  Yes  No

Cores Taken  Yes  No

Electric Log Run  Yes  No  
 (Submit Copy.)

List All E.Logs Run: CNL-CDL, DIL, MICRO, SONIC

Log Formation (Top), Depth and Datum  Sample  
 Name Top Datum

See Attached

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Conductor	14-3/4"	10-3/4"	29#	268'	60/40 Poz	225	3%cc 2%gel
Surface	19-7/8"	8-5/8"	24#	909'	Class A	150	3%cc 2%gel

ADDITIONAL CEMENTING/SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used) <input type="checkbox"/> Depth

TUBING RECORD		Size	Set At	Packer At	Liner Run <input type="checkbox"/> Yes <input type="checkbox"/> No
Date of First, Resumed Production, SWD or Inj.	Producing Method <input checked="" type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)				
Estimated Production Per 24 Hours	Oil Bbls. <u>N-A</u>	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity

Disposition of Gas: **METHOD OF COMPLETION** **Production Interval**

Vented  Sold  Used on Lease  Open Hole  Perf.  Dually Comp.  Commingled

(If vented, submit ACO-18.)  Other (Specify) \_\_\_\_\_

RELEAS  
 MAR 28 2001  
 FROM CONFIDENTIAL

ORIGINAL

CONF.

HUMMON CORPORATION

CONFIDENTIAL CONFIDENTIAL

Lease: Reed #1  
Spot: 250'North of NW NW  
County: Barber  
Contractor: Duke Drilling Rig #5  
Geologist: Arden Ratzlaff  
API # 15-007-22599-00-00

Prospect: Platt  
Section: 31-33s-15w  
State: Kansas

Elevation: G.L.= 1692  
K.B.= 1703

Tops	Sample		E- Log	
Herrington	2182	-479	2185	-482
Krider	2210	-507	2213	-510
Winfield	2253	-550	2255	-552
Towanda	2322	-619	2325	-622
Heebner	4013	-2310	4016	-2313
Lansing	4187	-2484	4188	-2485
Stark Shale	4525	-2822	4528	-2825
Mississippi	4799	-3096	4810	-3107
Viola	5115	-3412	5117	-3414
Simpson Sand	5303	-3600	5305	-3602
Arbuckle	5409	-3706	5407	-3704
RTD	5470	-3767	5472	-3769

KCC

SEP 16 1999

CONFIDENTIAL

DST #1 (Mississippi) 4783-4835. 30-60-30-60. 1st open, weak 1/2" blow decrease to surface blow. 2nd open, 1" blow decreased and died in 18 minutes. Recovered 30' of drilling mud. FP: 60-61/59-66. SIP: 98-73. BHT: 124.

DST #2 (Viola) 5169-5184. 30-60-30-60. 1st open, weak surface blow throughout. 2nd open, 1 1/2" blow that decreased to weak surface blow. Recovered: 30' GIP, 55' Gas cut muddy water, (chlorides 42,000 ppm) FP: 38-49/48-56. SIP: 1947-1930. BHT 133.

RELEASED

MAR 28 2001

FROM CONFIDENTIAL

RECEIVED  
KANSAS CORP COM  
1999 SEP 17 P 12:56

# ALLIED CEMENTING CO., INC.

2759

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
Medicine Lodge

ORIGINAL  
CONFIDENTIAL

DATE <u>8-16-99</u>	SEC. <u>31</u>	TWP. <u>33s</u>	RANGE <u>15w</u>	CALLED OUT <u>8:30 AM</u>	ON LOCATION <u>10:30 AM</u>	JOB START <u>12:45</u>	JOB FINISH <u>1:05 pm</u>
LEASE <u>Reed</u>	WELL # <u>1</u>	LOCATION <u>160' + Deerhead Rd. S; to 1st Y west to 1st</u>			COUNTY <u>Comanche</u>	STATE <u>Ks.</u>	
OLD OR <u>NEW</u> (Circle one)		Ad S, to Painted Post Rd. 1/2 E, 1/5					

CONTRACTOR <u>Duke Rig #5</u>	OWNER <u>Hummon Corp.</u>
TYPE OF JOB <u>Surface</u>	CEMENT
HOLE SIZE <u>14 3/4</u>	T.D. <u>270'</u>
CASING SIZE <u>10 3/4 x 29"</u>	DEPTH <u>268'</u>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX <u>200</u>	MINIMUM <u>-</u>
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG. <u>15 Feet</u>	
PERFS.	
DISPLACEMENT <u>25 1/2 Bbls Freshwater</u>	
EQUIPMENT	
PUMP TRUCK CEMENTER <u>Carl Balding</u>	
# <u>352</u> HELPER <u>Shane Winsor</u>	
BULK TRUCK	
# <u>301</u> DRIVER <u>Mark Brungardt</u>	
BULK TRUCK	
#	DRIVER
	TOTAL <u>\$1935.00</u>

KCC

SEP 16 1999

CONFIDENTIAL

REMARKS:

SERVICE

<u>Pipe on Bottom Breaks circulation.</u>	DEPTH OF JOB <u>268'</u>
<u>pump 3 Bbls freshwater.</u>	PUMP TRUCK CHARGE <u>470.00</u>
<u>pump 225 sx 60:40:3+2.</u>	EXTRA FOOTAGE @
<u>Release plug.</u>	MILEAGE <u>35</u> @ <u>2.85</u> <u>99.75</u>
<u>Displace with 25 1/2 Bbls freshwater.</u>	PLUG <u>Wooden 10 3/4"</u> @ <u>55.00</u> <u>55.00</u>
<u>Cement did circulate, shut IN.</u>	@
	@
	TOTAL <u>\$624.75</u>

CHARGE TO: Hummon Corp.  
STREET 950 N. TYLER  
CITY WICHITA STATE KANSAS ZIP 67212

FLOAT EQUIPMENT

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

TAX \_\_\_\_\_  
TOTAL CHARGE \$2559.75  
DISCOUNT 511.95 IF PAID IN 30 DAYS  
NET \$2047.80  
JOE HARRINGTON  
PRINTED NAME

RELEASED  
MAR 28 2001  
FROM CONFIDENTIAL

RECEIVED  
KANSAS CORP  
1999 SEP 17 P 12:56

# ALLIED CEMENTING CO., INC. 1946

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
med. lodge, Ks.

ORIGINAL  
CONFIDENTIAL

DATE <u>8-17-99</u>	SEC. <u>31</u>	TWP. <u>33S</u>	RANGE <u>15W</u>	CALLED OUT <u>12:00P.M.</u>	ON LOCATION <u>1:30P.M.</u>	JOB START <u>2:30P.M.</u>	JOB FINISH <u>5:30P.M.</u>
LEASE <u>Reed</u>	WELL # <u>1</u>	LOCATION <u>60+DeerHead ROAD, 205</u>			COUNTY <u>Comanche</u>	STATE <u>Ks.</u>	
OLD OR <u>NEW</u> (Circle one)		<u>5W-3S-1/2E-1/2A</u>					

KCC

SEP 16 1999

CONFIDENTIAL

CONTRACTOR <u>Duke Drq. #5</u>	OWNER <u>Hummon Corp.</u>
TYPE OF JOB <u>Plug Back</u>	CEMENT
HOLE SIZE <u>7 7/8</u>	T.D. <u>1010'</u>
CASING SIZE	DEPTH
TUBING SIZE	DEPTH
DRILL PIPE <u>4 1/2 x 16.60</u>	DEPTH <u>900'</u>
TOOL	DEPTH
PRES. MAX <u>200</u>	MINIMUM <u>100</u>
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	COMMON _____ @ _____
PERFS.	POZMIX _____ @ _____
DISPLACEMENT	GEL _____ @ _____
EQUIPMENT	CHLORIDE _____ @ _____
PUMP TRUCK CEMENTER <u>ARRY Drilling</u>	<u>Asc 100</u> @ <u>3.20</u> <u>320.00</u>
# <u>343</u> HELPER <u>Justin Hart</u>	<u>Kol-SEAL 500#</u> @ <u>.38</u> <u>190.00</u>
BULK TRUCK	HANDLING <u>100</u> @ <u>1.05</u> <u>105.00</u>
# <u>301</u> DRIVER <u>mark Brungardt</u>	MILEAGE <u>100 x 35</u> @ <u>.04</u> <u>140.00</u>
BULK TRUCK	TOTAL # <u>1255.00</u>
# DRIVER	

RELEASED  
MAR 28 2001

FROM CONFIDENTIAL

REMARKS:

SERVICE

Pipe set 900' possible loss Returns  
750'-770' load Hole 35 Bbs to load  
Cement w/ 100sxs. Asc + 5# Kol-Seal  
Displace w/ 6Bbs Fresh H<sub>2</sub>O. Pull  
Drill Pipe wait 2hrs. load Hole Tag  
Cement 837' Decide to Run 8 3/4" CSG

DEPTH OF JOB <u>900'</u>	
PUMP TRUCK CHARGE	<u>580.00</u>
EXTRA FOOTAGE	@ _____
MILEAGE <u>35</u>	@ <u>2.85</u> <u>99.75</u>
PLUG	@ _____
	@ _____
	@ _____
TOTAL	# <u>679.75</u>

CHARGE TO: Hummon Corp.  
STREET 950 N. TYLER  
CITY WICHITA STATE KANSAS ZIP 67212

FLOAT EQUIPMENT

_____	@ _____
_____	@ _____
_____	@ _____
_____	@ _____
_____	@ _____

TOTAL \_\_\_\_\_

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_  
TOTAL CHARGE 1934.75

DISCOUNT 386.95 IF PAID IN 30 DAYS  
NET # 1547.80

SIGNATURE [Signature]

X JOE LIVINGSTON  
PRINTED NAME

RECEIVED  
KANSAS CORP COMM.  
1999 SEP 17 P 12:58

# ALLIED CEMENTING CO., INC.

1947

Federal Tax I.D.# 48-0727860

REMIT TO PO. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
med. lodge, ks

ORIGINAL

CONFIDENTIAL

DATE <u>8-17-99</u>	SEC. <u>31</u>	TWP. <u>33s</u>	RANGE <u>15w</u>	CALLED OUT <u>8:30P.M.</u>	ON LOCATION <u>11:00P.M.</u>	JOB START <u>5:00A.M.</u>	JOB FINISH <u>6:00A.M.</u>
LEASE <u>Reed</u>	WELL # <u>1</u>	LOCATION <u>160+ Deerhead Rd. 6s-</u>			COUNTY <u>Comanche</u>	STATE <u>Ks.</u>	
OLD OR <u>NEW</u> (Circle one)		4w-5s					

CONTRACTOR Duke #5 OWNER Hummon Corp.

TYPE OF JOB Surface Csg.

HOLE SIZE 9 7/8 T.D. 936'

CASING SIZE 8 9/8 x 24 DEPTH 933'

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX 200 MINIMUM 100

MEAS. LINE \_\_\_\_\_ SHOE JOINT 38.90

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

CEMENT

AMOUNT ORDERED 150sxs. CLASS A

3% CC + 2% Gell + 1% Gyp Seal

COMMON	<u>150</u>	@ <u>6.35</u>	<u>952.50</u>
POZMIX		@	
GEL	<u>3</u>	@ <u>9.50</u>	<u>28.50</u>
CHLORIDE	<u>5</u>	@ <u>28.00</u>	<u>140.00</u>
		@	
		@	
		@	
		@	
		@	
HANDLING	<u>150</u>	@ <u>1.05</u>	<u>157.50</u>
MILEAGE	<u>150 x 35</u>	<u>.04</u>	<u>210.00</u>

TOTAL \$1488.50

EQUIPMENT

PUMP TRUCK CEMENTER Larry Drilling

# 343 HELPER Justin HART

BULK TRUCK

# 301 DRIVER Rick

BULK TRUCK

# \_\_\_\_\_ DRIVER \_\_\_\_\_

REMARKS:

Pipe on Bottom. Break Circ.  
mix + Pump 150sxs. CLASS A  
3% CC + 2% Gell + 1% Gyp Seal.  
Release Plug. Pump + Displace Plug  
w/ 26 1/2 Bbls. Fresh H<sub>2</sub>O. Bump Plug  
Shut In

SERVICE

DEPTH OF JOB	<u>933'</u>		
PUMP TRUCK CHARGE			<u>580.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>35</u>	@ <u>2.85</u>	<u>N/C</u>
PLUG Rubber 8 9/8"		@ <u>90.00</u>	<u>90.00</u>
		@	
		@	

TOTAL \$670.00

CHARGE TO: Hummon Corp.

STREET 950 N. TYLER

CITY WICHITA STATE KANSAS ZIP 67212

FLOAT EQUIPMENT

1-Baffle Plate	@ <u>45.00</u>	<u>45.00</u>
	@	
	@	
	@	
	@	

TOTAL \$45.00

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE X Joe Livingston

TAX \_\_\_\_\_

TOTAL CHARGE \$ 1062.80

DISCOUNT 1000 IF PAID IN 30 DAYS

Net # 1062.80

X Joe Livingston

PRINTED NAME

RELEASED  
MAR 28 2001  
FROM CONFIDENTIAL

KCC

SEP 16 1999

CONFIDENTIAL

# ALLIED CEMENTING CO., INC.

2521

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

GIBENS

ORIGINAL

CONFIDENTIAL

KCC

SEP 16 1999

CONFIDENTIAL

DATE <u>08-27-99</u>	SEC <u>31</u>	TWP <u>33S</u>	RANGE <u>5W</u>	CALLED OUT <u>9:30 AM</u>	ON LOCATION <u>2:00 AM</u>	JOB START	JOB FINISH <u>9:00 AM</u>
LEASE <u>REED</u>	WELL # <u>1</u>	LOCATION <u>160 + DEERHORN RD So to lat 4</u>			COUNTY <u>BARBER</u>	STATE <u>Ks</u>	
OLD OR NEW (Circle one)		<u>Went to lat rd So to park lot above rd 1/2 mi S</u>					

CONTRACTOR <u>Duke Dalg. Rg #5</u>	OWNER <u>HUMMON CORP.</u>																																																																						
TYPE OF JOB <u>ROTARY PLUG</u>																																																																							
HOLE SIZE <u>7 7/8"</u>	T.D. <u>15470'</u>																																																																						
CASING SIZE	DEPTH																																																																						
TUBING SIZE	DEPTH																																																																						
DRILL PIPE	DEPTH																																																																						
TOOL	DEPTH																																																																						
PRES. MAX	MINIMUM																																																																						
MEAS. LINE	SHOE JOINT																																																																						
CEMENT LEFT IN CSG.																																																																							
PERFS.																																																																							
DISPLACEMENT																																																																							
<b>EQUIPMENT</b>																																																																							
PUMP TRUCK # <u>120</u>	CEMENTER <u>BJD</u>																																																																						
	HELPER <u>JD</u>																																																																						
BULK TRUCK # <u>341</u>	DRIVER <u>BLAINE</u>																																																																						
BULK TRUCK #	DRIVER																																																																						
<table border="0"> <tr> <td>COMMON</td> <td><u>135 cu</u></td> <td>@</td> <td><u>6.25</u></td> <td><u>857.25</u></td> </tr> <tr> <td>POZMIX</td> <td><u>90 cu</u></td> <td>@</td> <td><u>3.25</u></td> <td><u>292.50</u></td> </tr> <tr> <td>GEL</td> <td><u>12 cu</u></td> <td>@</td> <td><u>9.50</u></td> <td><u>114.00</u></td> </tr> <tr> <td>CHLORIDE</td> <td></td> <td>@</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td>@</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td>@</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td>@</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td>@</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td>@</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td>@</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td>@</td> <td></td> <td></td> </tr> <tr> <td>HANDLING</td> <td><u>225 cu</u></td> <td>@</td> <td><u>1.05</u></td> <td><u>236.25</u></td> </tr> <tr> <td>MILEAGE</td> <td><u>225 cu</u></td> <td>@</td> <td><u>04 35</u></td> <td><u>315.00</u></td> </tr> <tr> <td colspan="4"></td> <td>TOTAL <u>1815.00</u></td> </tr> </table>		COMMON	<u>135 cu</u>	@	<u>6.25</u>	<u>857.25</u>	POZMIX	<u>90 cu</u>	@	<u>3.25</u>	<u>292.50</u>	GEL	<u>12 cu</u>	@	<u>9.50</u>	<u>114.00</u>	CHLORIDE		@					@					@					@					@					@					@					@			HANDLING	<u>225 cu</u>	@	<u>1.05</u>	<u>236.25</u>	MILEAGE	<u>225 cu</u>	@	<u>04 35</u>	<u>315.00</u>					TOTAL <u>1815.00</u>
COMMON	<u>135 cu</u>	@	<u>6.25</u>	<u>857.25</u>																																																																			
POZMIX	<u>90 cu</u>	@	<u>3.25</u>	<u>292.50</u>																																																																			
GEL	<u>12 cu</u>	@	<u>9.50</u>	<u>114.00</u>																																																																			
CHLORIDE		@																																																																					
		@																																																																					
		@																																																																					
		@																																																																					
		@																																																																					
		@																																																																					
		@																																																																					
		@																																																																					
HANDLING	<u>225 cu</u>	@	<u>1.05</u>	<u>236.25</u>																																																																			
MILEAGE	<u>225 cu</u>	@	<u>04 35</u>	<u>315.00</u>																																																																			
				TOTAL <u>1815.00</u>																																																																			

REMARKS:

SERVICE

<u>1 1/2" DP HALVING AT 900' Vertical</u>	DEPTH OF JOB	<u>900 Ft</u>
<u>Mixed 50 cu 60/40 Poz 6% Gel</u>	PUMP TRUCK CHARGE	<u>470.00</u>
<u>Drained 4 Bls Mixed 2nd Pump 4 1/2 3rd</u>	EXTRA FOOTAGE	@
<u>Mixed 40 cu 60/40 Poz 6% Gel Pump 3</u>	MILEAGE	<u>35 @ 2.85 99.75</u>
<u>For Freshen to Plug 10' 7 1/2" ID</u>	PLUG	@
<u>10 cu 60/40 6% - 10 cu 15 cu</u>		@
<u>60/40 6 1/2 Poz 6% 10 cu 60/40 6%</u>		@
<u>8 5/8" x 10 3/4 Annulus mixed 100 cu</u>		@
<u>60/40 6% 350 # PSI.</u>		
		TOTAL <u>569.75</u>

CHARGE TO: HUMMON CORP.  
STREET 950 N. TULEA  
CITY WICHITA STATE Ks ZIP 67212

FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	
		TOTAL

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

TAX \_\_\_\_\_  
TOTAL CHARGE \$ 2384.75  
DISCOUNT 476.95 IF PAID IN 30 DAYS  
Net 1907.80  
JOE DRIVINGSTON  
PRINTED NAME

FROM CONFIDENTIAL  
MAR 28 2001  
RELEASED