

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Murfin Drilling Company
ADDRESS 617 Union Center Bldg.
Wichita, Ks 67202

API NO. 15-007-21,416 -00-00
COUNTY Barber
FIELD Wildcat

\*\*CONTACT PERSON Ramona Gunn
PHONE 267-3241


PROD. FORMATION
LEASE Landwehr.

PURCHASER
ADDRESS

WELL NO. 1-27

WELL LOCATION 750'FNL 930'FEL
750 Ft. from North Line and
930 Ft. from East Line of
the NE SEC. 27 TWP. 33 RGE. 15W

WELL PLAT



KCC
KCS
(Office Use)

PLUGGING Eagle Drilling, Inc.
CONTRACTOR
ADDRESS P.O. Box 8609
Wichita, KS 67208

TOTAL DEPTH 4981 PBTD

SPUD DATE 3-11-82 DATE COMPLETED 3-26-82

ELEV: GR 1802 DF 1812 KB 1815

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Amount of surface pipe set and cemented 430' DV Tool Used? No

AFFIDAVIT

STATE OF Kansas, COUNTY OF Sedgwick SS, I, David

L. Murfin OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS Drilling Manager (FOR)(OF) Murfin Drilling Company

OPERATOR OF THE Landwehr LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1-27 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 12th DAY OF April, 1982, AND THAT

ALL INFORMATION REFERRED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIRMATION NOT.
Wichita Kansas

SUBSCRIBED AND SWORN BEFORE ME THIS 12th DAY OF April 1982

RAMONA GUNN
STATE NOTARY PUBLIC
Sedgwick county, Kansas
My Appt. Exp.

MY COMMISSION EXPIRES: Jan. 25, 1984

NOTARY PUBLIC
Ramona Gunn

\*\*The person who can be reached by phone regarding any questions concerning this information. Within 45 days of completion, a witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Well Log			LOG TOPS	
Surface Soil & Sand		100	Herrington	2220 (-405)
Red Bed		1179	Towanda	2372 (-557)
Shale & Shells		3033	B/Florence	2528 (-713)
Shale & Lime		4420	Cottonwood	2784 (-969)
Lime	RTD	4981	Admire	3032 (-1217)
			Indian Cave	3094 (-1279)
			Wabunse	3132 (-1317)
			Stotler	3290 (-1475)
			Tarkio	3349 (-1534)
			LeCompton	3836 (-2021)
			Oread	4025 (-2210)
			Heebner	4062 (-2247)
			Toronto	4079 (-2264)
			Douglas	4104 (-2289)
			Lansing	4761 (-2446)
			BKC	4698 (-2883)
			Mississippian	4884 (-3069)

Report of all strings set — surface, intermediate, production, etc. **CASING RECORD** (New) or ~~(Used)~~

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8-5/8	24#	430	Common	275	3% CC, 2% Gel

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

**TUBING RECORD**

Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
<b>RATE OF PRODUCTION PER 24 HOURS</b>	Oil bbls.	Gas MCF
	Water %	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)		Perforations