

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-007-21755-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Woolsey Petroleum Corp. KCC LICENSE # 5506 <sup>6/97</sup>  
(owner/company name) (operator's)

ADDRESS 107 N. Market #600 CITY Wichita

STATE KS ZIP CODE 67202 CONTACT PHONE # (316) 886-5606

LEASE Mills Feed WELL# A-1 SEC. 24 T. 31 R. 14W (East/West)

C - SE - SE - SE SPOT LOCATION/QQQQ COUNTY Barber

330 FEET (in exact footage) FROM (S) N (circle one) LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM (E) W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL \_\_\_ GAS WELL XX D&A \_\_\_ SWD/ENHR WELL \_\_\_ DOCKET# \_\_\_

CONDUCTOR CASING SIZE \_\_\_ SET AT \_\_\_ CEMENTED WITH \_\_\_ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 393 CEMENTED WITH 250 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 3849' CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3772'-3780'

ELEVATION 1643'/1657' T.D. 3850 P.B.T.D. 3835' ANHYDRITE DEPTH \_\_\_  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD XX POOR \_\_\_ CASING LEAK \_\_\_ JUNK IN HOLE \_\_\_

PROPOSED METHOD OF PLUGGING Place sand @ 3722 and spot 4 sacks cement w/bailer.

cut and lay down 4 1/2". Down 8 5/8", pump 300# cottonseed hulls + 10 sacks

gel + 50 sacks cement + 10 sacks gel + 100# hulls + 8 5/8" plug + 100 sacks

(If additional space is needed attach separate page) cement 60/40 poz + 6% gel.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? XX IS ACO-1 FILED? yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Carl W. Durr PHONE# (316) 886-5606

ADDRESS P.O. Box 168 City/State Medicine Lodge, KS 67104

PLUGGING CONTRACTOR Clarke Corp. KCC LICENSE # 122270 <sup>5105</sup> <sup>6/97</sup>  
(company name) (contractor's)

ADDRESS Medicine Lodge, KS PHONE # (316) 886-5665

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 10/24/96 8:00A.M.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-5-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 09/27/96 AUTHORIZED OPERATOR/AGENT: Carl W. Durr  
(signature)



## Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner  
Judith McConnell, Executive Director David J. Heinemann, General Counsel

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

September 30, 1996

Woolsey Petroleum Corporation  
107 N Market #600  
Wichita KS 67202

Mills Feed A-1  
API 15-007-21,755-0000  
330 FSL 330 FEL  
Sec. 24-31S-14W  
Barber County

Dear Carl W. Durr,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760