


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Barber County, Sec. 6 Twp. 33 Rge. 12 (E) (W)



Location as "NE/CNW&SW" or footage from lines C, SE NE
Lease Owner Parker Petroleum Co., Inc.
Lease Name Alexander Well No. 1
Office Address P. O. Drawer 791, Ponca City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed 3-9 19.51
Application for plugging filed 5-22 19.57
Application for plugging approved 5-23 19.57
Plugging commenced 5-26 19.57
Plugging completed 5-30 19.57
Reason for abandonment of well or producing formation reduced production

If a producing well is abandoned, date of last production October 19.56
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Risse
Producing formation Douglas SS Depth to top 3885 Bottom 3895 Total Depth of Well 3895 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Elgin		3680		10 3/4	204'	
Douglas	Gas	3885	3895	5 1/2	3881	2612'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Lane Wells set plug @ 3792' dumped two sacks cement on top of plug, set bridge plug @ 205' filled hole to 170' with chunk mud, filled 155' with rock and mixed and poured 25 sacks of cement filled up to 40' of top with chunk mud 30' mixed up 10 sacks of cement, capped top of surface and took surface head off.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Smith and Smith Casing Pulling Co.
Address Duncan, Oklahoma

STATE OF Oklahoma, COUNTY OF Kay, ss.
Charlotte J. Boone (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Charlotte J. Boone (Geol.)*
Ponca City, Oklahoma (Address)

SUBSCRIBED AND SWORN TO before me this 10th day of June, 19 57

My commission expires July 31, 1960

Carl B. Romer
Notary Public.

PLUGGING
FILE SEC 6 T 33 R 12W
BOOK PAGE 14 LINE 38

RECEIVED
STATE CORPORATION COMMISSION

JUN 11 1957
CONSERVATION DIVISION
Wichita, Kansas

ALEXANDER #1

Company: Parker Petroleum Co., Inc.
 Contractor: Gabbert-Jones Drilling Co.

Location: C SE NE
 Sec. 6-33S-12W
 Barber County
 Kansas

Commenced: 2-21-51
 Completed: 3-9-51

Elevation: DF 1684
 KB 1687

Total Depth: 3895'

Casing: 204' of 13 3/4" w/ 100 sx.
 3881' of 5 1/2" w/ 500 sx.

FIGURES INDICATE BOTTOM OF FORMATIONS

<u>Formation</u>	<u>Depth</u>
Red Bed and Gyp	0 - 60
Red Bed	60 - 629
Red Bed and Sh.	629 - 860
Shale and Shells	860 - 1350
Lime and sh.	1350 - 1745
Broken Lime	1745 - 1780
Lime	1780 - 2330
Broken Lime	2330 - 2350
Lime Sdy	2350 - 2410
Sh.	2410 - 2450
Lime	2450 - 2515
Shale	2515 - 2585
Sh & Lm	2585 - 3075
Broken Lime	3075 - 3200
Lime	3200 - 3535
Shale	3535 - 3580
Sh & lm strks.	3580 - 3650
Lime and Sh.	3650 - 3875
Sh.	3875 - 3885
Sd.	3885 - 3895
Total Depth	3895

We hereby certify that the above and foregoing is a true and correct copy of the Log on the Alexander #1, Barber County, Kansas.

PARKER PETROLEUM CO., INC.

By _____

Subscribed and sworn to before me this _____ day of _____, 1957.

Notary Public:

My commission expires:

RECEIVED
 CORPORATION COMMISSION

MAY 23 1957

PLUGGING
 FILE SEC. 6 T. 33 12W
 BOOK PAGE 14 ERW 30

CONSERVATION DIVISION
 Wichita, Kansas