

DeGeer Well No. 1

NE NE NE
Sec. 4-33S-15W
Barber County, Kansas

Contractor: R. W. Rine Drilling Company

Started: 8/23/49

Finished: 9/20/49

Log

Sand, red bed	0- 125	
Sand, red bed	125- 150	Cemented Lost Circ. w/ 110 sx.
Cement	60- 150	50 sx. @ 5 P.M. & 50 sx. @ 8 P.M.
Red bed, shells	150- 480	
Hard sand	480- 505	8-5/8" @ 504' w/ 300 sx. - Circ.
Cement	470- 504	
Sand, shale	504- 730	
Red bed, shale	730- 990	
Salt, shale	990-1325	
Red bed, shale	1325-1780	
Shale	1780-1810	
Shale, shells	1810-2025	
Lime, shale	2025-2410	
Lime, shale	2410-2795	
Shale	2795-2930	
Shale, shells	2930-3020	
Shale	3020-3290	Lost mud @ 3240'
Shale, lime	3290-3380	
Shale	3380-3895	
Shale, lime	3895-3955	Lost returns @ 3946'
Shale	3955-4029	
Shale, lime	4029-4085	
Shale	4085-4164	
Shale, lime	4164-4260	Lost returns @ 4199'
Lime	4260-4520	
Lime, shale	4520-4538	
Lime	4538-4637	
Lime, shale	4637-4670	
Lime	4670-4770	
Lime, shale	4770-5016	
Lime	5016-5046	
Lime, cherty	5046-5065	
Lime	5065-5094	
Lime, shale	5094-5115	
Shale, sand	5115-5135	
Sand	5135-5140	
Core #1 - sand	5140-5152	
Sand	5152-5160	
Sand, shale	5160-5219	
Shale, lime	5219-5251	
Shale, arbuckle	5251-5300	
Lime	5300-5306	

Elevation: 1907 KB

Kansas City	4233'
Mississippi	4895'
Viola	4991'
Simpson	5129'
Sand	5137'
Arbuckle	5248'

State of Kansas)
County of Sedgwick)ss

I, E. H. Sloyer, do hereby certify that the above is a true and accurate log on the DeGeer No. 1 well located in the NE NE Sec. 4-33S-15W, Barber County, Kansas.

Sworn to and subscribed before me this 23rd day of September, 1949.

E. H. Sloyer
Secretary

R. M. Green
Notary Public

My commission expires December 29, 1952.

