

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-007-20163-00-00

API NUMBER JAN 14, 1971

LEASE NAME BRASS

WELL NUMBER # 1

2970 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 5 TWP. 33S RGE. 15 (E) or (W)

COUNTY BARBER

Date Well Completed 1/14/71

Plugging Commenced 6/18/86

Plugging Completed 6/25/86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Champlin Petroleum Company

ADDRESS 6441 N. Grand Blvd. OKA CITY, OKIA 73116

PHONE# (405) 840 5521 OPERATORS LICENSE NO. 6417

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? DODGE CITY KANSAS

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation KANSAS CITY - Lansing Depth to Top 4362 Bottom 4825 T.D. 5085

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				13"	292'	NONE
				5 1/2"	5076'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

MIX AND PUMP 1 SACK COTTON SEED HULL. MIX AND PUMP 20 SACKS 50 MIX CEMENT (13 3/4 bbls. of surry) MIX AND PUMP 17 SACKS TELL 69 bbl. OF 9lb. MUD, FOLLOW 33 SACKS THIRTY MIX CEMENT (22 bbl. OF SURRY) FILL HOLE SQUEEZE 1500lb. Release pressure Hook up to surface pipe mix and pump 56 SACKS OF CEMENT. (20 bbls. surry) AT 200 lb pressure SF

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B. J. TITAN License No. 1111 - 3 1986

Address MEDICINE LODGE KANSAS

CONSERVATION DIVISION
Wichita, Kansas

STATE OF OKIA COUNTY OF OKIA, ss.

Steve Harwell (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Steve Harwell
(Address) 6441 N. Grand Blvd OKA CITY, OKIA 73116

SUBSCRIBED AND SWORN TO before me this 2nd day of July, 19 86

Notary A. Owens
Notary Public

My Commission Expires: 10-08-87