

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 COLORADO DERRY BUILDING  
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-007-21,706-00-00

LEASE NAME Mitchell

WELL NUMBER 1-16

SPOT LOCATION S/2 SW SW

SEC. 16 TWP. 33 SRGE. 15 (X) OR (W)

COUNTY Barber

DATE WELL COMPLETED 12-1-83

PLUGGING COMMENCED 12-1-83

PLUGGING COMPLETED 12-1-83

TYPE OR PRINT  
PLEASE FILL OUT COMPLETELY  
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Westmore Drilling Co.

ADDRESS Chapin Building, Medicine Lodge, Ks. 67104

PHONE # (316) 886-5611 OPERATORS LICENSE NO. 6769

CHARACTER OF WELL Dry Hole  
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Maurice Leslie, Nashville, Kansas

IS ACC-1 FILED? Yes IF NOT, IS WELL LOG ATTACHED? \_\_\_\_\_

PRODUCING FORMATION \_\_\_\_\_ DEPTH TO TOP \_\_\_\_\_ BOTTOM T.D. 4836

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE    | PUT IN | PULLED OUT |
|-----------|---------|------|----|---------|--------|------------|
|           |         |      |    | 10-3/4" | 258'   | None       |
|           |         |      |    | 8-5/8"  | 1282'  | None       |
|           |         |      |    |         |        |            |
|           |         |      |    |         |        |            |

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.  
1st plug @ 1320' with 40 sacks 60-40 posmix, 2% Gel, 3% CC thru drill pipe  
2nd plug @ 450' with 40 sacks as above  
Hulls, bridge & plug @ 40' with 10 sacks as above. Plugged rat hole with 15 sacks cement.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Graves Drilling Co., Inc. LICENSE NO. 5428  
ADDRESS 910 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, SS.

Betty Brandt (EMPLOYEE OF OPERATOR) OR  
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT  
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND  
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND  
CORRECT, SO HELP ME GOD.

(SIGNATURE) Betty Brandt

(ADDRESS) 910 Union Center, Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO BEFORE ME THIS 19 DAY OF December, 1983



Tricia K. Glidewell  
NOTARY PUBLIC  
Tricia K. Glidewell

MY COMMISSION EXPIRES: March 16, 1986

FORM CP-4  
REVISED 06-83  
Wichita, Kansas  
CONSERVATION DIVISION

JAN 09 1984  
RECEIVED  
STATE CORPORATION COMMISSION