

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Barber SEC. 24 TWP. 31S RGE. 14W E/W
 Location as in quarters or footage from lines:
C N/2 NW/4

Lease Owner Hummon Oil Company
 Lease Name Mott Well No. #1
 Office Address Suite 400 One Main Place - Wichita, KS 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Gas
 Date Well Completed 8-3-78
 Application for plugging filed 3-31-82
 Plugging commenced 5-1-82
 Plugging completed 5-5-82
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt:

Dry
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. V. Leslie
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3,015

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				13 3/8	236	None
				4 1/2	2893	2187

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Sand from 2,800 to 2,600
4 sacks cement from 2,600 to 2,570
Ripped at 2,400 and 2,187

Allied pumped in 15 jell - 6 hull - 10 jell
200 sacks ccement 3% C. C.

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 11 1982
 5-11-82
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barber, ss.
Elmo R. Morgustern (employee of ~~owner~~) or (~~owner or operator~~) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Elmo R. Morgustern
Wichita, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 7th day of May, 1982.

Jessie Hamilton
 Notary Public.

My Commission expires: April 4, 1986

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Mott #1
 C-N/2-NW4 Sec 24-31S-13W
 Barber County Kansas

Commenced: 7-28-78

Completed: 8-3-78

OPERATOR: HUMMON OIL CO.

Depth		Formation	Remarks
From	to		
0	60	Sand-Clay	Ran 6 jts of 48# 13 3/8" csg
60	610	Redbed	set @ 236' Cemented w/
610	1565	Shale	250 sks Common 2% Gel
1565	2740	Shale-Lime	3% CC PD @ 1:00 a.m. 7-29-78
2740	3015	Lime-Shale	1" to 40' w/60 sks Common 3% CC Complete @ 4:30 a.m. 7-29-78
	3015 - TD		Ran 72 jts of 10# 4 1/2" csg set @ 2893' w/125 sks 60/40 Posmix 18% Salt 3/4 of 1% CFR-2 15 bbls Flush PD @ 6:00 a.m. 8-3-78

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
 Drillers' Well Log is true and correct to the best of my knowledge and belief and
 according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me this 8th day of August, 1978.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.

