


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County, Sec. 24 Twp. 31 Rge. 14 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C of NW NW
Lease Owner Sohio Petroleum Co.
Lease Name Mott #1 Well No.
Office Address Russell, Kansas 67665
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 12/9/76 19
Plugging completed 12/11/76 19
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4608
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	213	none
				4 1/2"	2976	2015'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed plug to 2675' and sanded to 2650', ran 4 sacks cement. Shot pipe at 2005', pulled 60 joints. Mudded hole to 200' and set 10' rock bridge. Filled hole with 3 yards ready mix from 190 to base of cellar.

PLUGGING COMPLETE.

DEC 15 1976

12-15-76
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

R. Darrell Kelso
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of December, 1976

Margaret Melcher
Notary Public.

My commission expires



15-007-20274-0000

WELL LOG

COMPANY **Sohio Petroleum**

SEC. 24 T. 31S R. 14W

FARM **Mott**

NO. **1**

LOC. **NW NW**


TOTAL DEPTH **4608'**

COUNTY **Barber, Kansas**

COMM. **7-27-74**

COMP. **8-18-74**

CONTRACTOR **DaMac Drilling Company, Inc.**



CASING **3 5/8" @ 213' with 175/aks.**

4 1/2" @ 2976 with 250/aks.

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

210	Sand & Red Bed
1280	Red Bed & Shale
1367	Shale
1630	Shale & Shells
1900	Lime & Shale
3839	Lime
3993	Lime & Shale
4140	Lime
4608	RTD < B

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1976
11-18-76
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } SS

I, Martha J. McKown of DaMac Drilling Company, Inc.

upon oath state the above and foregoing is a true and correct copy of the log of the Mott No. 1 well.

CHARLENE M. MARKER
NOTARY PUBLIC
Barton County, Kansas
My Commission Expires
September 13, 1977

Martha J. McKown

Subscribed and sworn to before me this 21st day of August 19 74

My Commission Expires: Sept. 13, 1977

Charlene M. Marker
NOTARY PUBLIC