


15-007-00586-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 23 Twp. 31 Rge. (E) 14 (W)
Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Aylward Drilling Company
Lease Name Lake "C" Well No. 1 X
Office Address 813 1st Nat'l Bank Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 13 19 58
Application for plugging filed July 13 19 58
Application for plugging approved July 13 19 58
Plugging commenced July 13 19 58
Plugging completed July 13 19 58
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4618 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	846'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from total depth to 180'; set Halliburton plug and used 1/2 sack of hulls and 20 sacks of cement from 180' to 130'; heavy mud from 130' to 40'; set Halliburton plug and used 1/2 sack of hulls and 10 sacks of cement to fill to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
7-22-58
JUL 22 1958
CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor Aylward Drilling Company
Address 813 1st National Bank Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Paul W. Hesse (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W Hesse

(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of July, 1958

My commission expires December 11, 1961

Duane Jessup Notary Public

PLUGGING
FILE SEC 23 T 31 R 14W
BOOK PAGE 115 LINE 21

LAKE "C" NO. 1 x

Casing Record: 8 5/8" - 846'
 Company: Aylward Drilling Company
 Contractor: Aylward Drilling Company
 Location: NW NW NW 23-31-14W
 Barber County,
 Kansas
 Commenced: June 28, 1958
 Completed: July 13, 1958
 Elevation: 1618' DF

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Soil	0	20	Set 8 5/8" @ 846' w/450 sacks cement.
Sand	20	45	
Red Rock & Shale	45	435	Geological Tops:
Red Bed & Shale	435	935	
Salt	935	985	Heebner 3597
Shale & Lime	985	1315	Base/Oread 3630
Shale & Shells	1315	1575	Tonganoxie Sand 3737
Shale & Lime	1575	1785	Lansing 3759
Lime w/Shale Streaks	1785	1965	B/Kansas City 4199
Lime	1965	2115	Massey 4220
Lime w/some Shale	2115	2300	Mississippian 4291
Lime	2300	2575	Kinderhood 4323
Lime & Shale	2575	2800	Viola 4386
Shale & Lime	2800	2950	Simpson 4524
Lime & Shale	2950	3100	Arbuckle 4583
Lime	3100	3355	R.T.D. 4618
Lime & Sandy Shale	3355	3500	
Lime & Shale	3500	3718	DST 4208-41 Open 30 Min. Very wk. bl./1"
Sand	3718	3730	Rec. 10' mud. IBHP 0#/20", FBHP 0#/20"
Sandy Shale & Lime	3730	3745	FP 0#-0#.
Lime & Shale	3745	3845	
Lime	3845	4241	DST 4374-87 Open 45 min. Very wk. bl./4"
Lime w/some Shale	4241	4270	Rec. 15' mud. IBHP 1980#/20", FBHP 85#/20"
Cherty Lime	4270	4303	FP 40#-44#.
Chert & Lime	4303	4340	
Cherty Lime	4340	4355	
Lime & Shale	4355	4382	
Lime	4382	4416	
Lime (Cherty)	4416	4487	
Lime & Shale	4487	4497	
Lime & Shale w/Chert	4497	4525	
Sandy Lime	4525	4595	
Lime w/Shale Streaks	4595	4618 T.D.	

D & A

RECEIVED
 STATE CORPORATION COMMISSION

JUL 22 1958
 7-22-58
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesse

Subscribed and sworn to before me this 17th day of July, 1958.

Duane Jessup
 DUANE JESSUP Notary Public

My Commission expires December 11, 1961.

PLUGGING
 FILE SEC 23 T 31 R 14W
 BOOK PAGE 115 LINE 21