

15-007-05585-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barber County, Sec. 23 Twp. 31 Rge. 14 (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Aylward Drilling Company
Lease Name Lake "C" Well No. 1
Office Address 813 1st Nat'l Bank Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole (Lost hole)
Date well completed June 28 1958
Application for plugging filed June 28 1958
Application for plugging approved June 28 1958
Plugging commenced June 28 1958
Plugging completed June 28 1958
Reason for abandonment of well or producing formation Lost hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp - Stafford, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 1685 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	194'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud from total depth to 180'; plug at 180' with 1/2 sack of hulls and 20 sacks of cement; heavy mud to 40'; top plug from 40' to top of surface with 1/2 sack of hulls and 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1958
7-22-58
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Aylward Drilling Company
Address 813 First National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Paul W. Hesse (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse
813 1st Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of July, 1958

My commission expires February 27, 1960.
Mildred F. Willis
Notary Public.

PLUGGING
FILE SEC 23 T. 31 R. 14 W.
BOOK PAGE 112 LINE 20

LAKE "C" NO. 1

Casing Record: Company: Aylward Drilling Company Location: NW NW NW 23-31-14W
 8 5/8" - 190' Contractor: Aylward Drilling Company Barber County, Kansas
 Commenced: June 25, 1958
 Completed: June 27, 1958 (Skid Rig) Elevation: 1618 DF

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay & Sand	0	35	Set 8 5/8" surface pipe @ 190' w/200 sacks cement.
Sand	35	50	
Red Bed & Clay	50	120	
Red Bed & Gypsum Shells	120	171	
Red Rock & Gyp	171	680	
Red Rock & Shale	680	856	
Shale & Shells	856	935	
Salt	935	985	
Shale & Shells	985	1450	
Shale & Anhydrite	1450	1665	
Shale & Lime	1665	1685	Hole failed - skidded rig.

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hess

Subscribed and sworn to before me this 16th day of July, 1958.

Duane Jessup
 DUANE JESSUP Notary Public

My commission expires December 11, 1961.

RECEIVED
 STATE CORPORATION COMMISSION
 7-22-58
 JUL 22 1958

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING	
FILE	SEC. 23 T. 31. R. 14W
BOOK	PAGE 112 LINE 20