

COCONUT DRILLING, INC.

Mark L. Haas, Owner

October 30, 1981

316-625-2490

316-625-2139

711 South Grove

Yates Center, Kansas 66783

15-207-23228-00-00 BEM

Steinforth-Haas
Yates Center, KS
Lauber Lease, Well #1
Sec., 7, Twp 26, Rg. 15E
Woodson County, Kansas

Comm. 10-27-81

Comp. 10-28-81

Formation:

Soil	0	-	2	Shale	602	-	606
Clay	2	-	6	Lime BKC	606	-	663
Red Clay	6	-	8	Shale	663	-	760
Clay	8	-	17	Lime	760	-	762
Sandy Shale	17	-	22	Shale w/ Lime Streaks	762	-	785
Shale	22	-	166	Lime	785	-	808
Lime	166	-	192	Shale	808	-	822
White Sandy Lime	192	-	214	Lime	822	-	845
Lime	214	-	221	Shale	845	-	909
Sandy Shale	221	-	225	Lime	909	-	940
Lime	225	-	258	Shale	940	-	945
White Sandy Lime	258	-	265	Lime	945	-	954
Lime	265	-	341	Shale	954	-	965
Shale	341	-	352	Lime 20'	965	-	984
Lime	352	-	355	Black Shale	984	-	990
Shale	355	-	369	Lime 5'	990	-	996
Lime	369	-	378	Black Shale	996	-	1002
Shale	378	-	385	Shale	1002	-	1160
White Sandy Lime	385	-	416	Black Shale	1160	-	1172
Lime	416	-	434	Shale	1172	-	1193
Sandy Shale	434	-	457	Water Sand	1193	-	1205
Shale	457	-	502	Shale	1205	-	1244
Shale w/Lime	502	-	506	Sandy Shale	1244	-	1291
Shale	506	-	509	Shale	1291	-	1300
Lime	509	-	522				
White Sandy Lime	522	-	528				
Lime	528	-	602				

Total Depth 1300'

Dry Hole

Plugged 10-28-81

12 Sks at 250'

10 Sks at 50'

RECEIVED
STATE CORPORATION COMMISSION

NOV 5 1981

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-207-23228-00-00 BEM

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Woodson County, Sec. 7 Twp. 26 Rge. 15 E/W
Location as "NE/CNW1SW1" or footage from lines
2050 750'- S. Line, 1170' W. Line


Lease Owner Steinforth-Haas
Lease Name Lauber Lease Well No. #1
Office Address 711 S. Grove, Yates Center, KS
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed 10-28-81 19
Application for plugging filed 10-28-81 19
Application for plugging approved 10-28-81 19
Plugging commenced 10-28-81 19
Plugging completed 10-28-81, 7:30 PM 19
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Merle Hickey
Producing formation Depth to top 1300' Bottom Total Depth of Well
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

12 Sacks Portland Cement at 250'
10 Sacks Portland Cement at 50' to top of hole.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Mark L. Haas, Coco nut Drilling, Inc.

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS
5 1981

STATE OF KANSAS COUNTY OF WOODSON
Mark L. Haas (Employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Mark L. Haas
711 S. Grove, Yates Center, KS 66783 (Address)

SUBSCRIBED AND SWORN TO before me this 30th day of October, 19 81

Deborah S. Haas
Deborah S. Haas Notary Public.

My commission expires 12/21/83

