

15-077-20084-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Harper County, Sec. 36 Twp. 32S Rge. (E) 9 (W)

Location as "NE/CNW/SW" or footage from lines C SE SE
Lease Owner William H. Pine
Lease Name Oliver Well No. 1
Office Address Okmulgee, Oklahoma 74447
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 11, 19 69
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced April 11, 19 69
Plugging completed April 11, 19 69
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Ralph Warren of Pratt)

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 4782 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	250'	8-5/8"	3/31/69	-----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 240 Feet;
1/2 sax Hulls, Plug and 25 sax Cement thru
the Drill Pipe; Mud to 40 Feet; 1/2 sax
Hulls, Plug and 10 sax Cement to Base
of Cellar; 2 sax Cement in Rat Hole.
Job completed @ 12:30 P.M. 4/11/69.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co., Inc.
Address 500 Bitting Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Wayne W. Kahmeyer of Sage Drilling Co. (employee of owner) or (owner or operator) of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer
500 Bitting Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 15th day of April 19 69

My commission expires November 26, 1970.

Louise K. Whitted - Notary Public.



DRILLERS LOG

OLIVER NO. 1

CASING RECORD:	OPERATOR: William H. Pine	DESCRIPTION:
8-5/8" @ 250' w/200 sax cement	CONTRACTOR: Sage Drilling Co.	C SE SE Sec. 36-32S-9W Harper County, Kansas
TOTAL DEPTH: 4782'	COMMENCED: March 31, 1969	
	COMPLETED: April 11, 1969	


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	252	
Shale & Shells	252	850	
Shale, Shells, Salt & Lime	850	1470	
Shells, Shale & Lime	1470	1750	
Lime & Shale	1750	1965	
Shale & Lime	1965	2315	
Lime & Shale	2315	3363	
Lime, Shale & Sand	3363	3955	
Lime & Shale	3955	4015	
Lime	4015	4080	
Lime & Shale	4080	4400	
Mississippi	4400	4614	
Kinderhook Shale	4614	4653	
Kinderhook & Chat	4653	4692	
Chat	4692	4720	
Viola	4720	4782	D&A

RECEIVED
STATE CORPORATION COMMISSION
APR 16 1969
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer
Wayne W. Kahmeyer



Subscribed and sworn to before me this 14th day of April, 1969.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.