

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-21,138-0000

LEASE NAME Kinser

WELL NUMBER 2

2020 Ft. from S Section Line

440 Ft. from E Section Line

SEC. 36 TWP. 32 RGE. 9 ~~XKRXK~~(W)

COUNTY Harper

Date Well Completed _____

Plugging Commenced 2-24-97

Plugging Completed 2-28-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR KBW Oil & Gas Company

ADDRESS P.O. Box H, Bethany, OK 73008

PHONE# (405) 789-0178 OPERATORS LICENSE NO. 5993

Character of Well Good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-24-97 (date)

by Woolrly (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? yes

Producing Formation N/A Depth to Top 2777 Bottom 2779 T.D. 3087

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	239	None
				5 1/2	3087	1950

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from feet to feet each s
Lay down rods and tubing, sand well back to 2695, dump 5sx portland cement with dump bailor, stretch and cut casing at 1950, lay down casing, tally and run 2 3/8 tubing to 1307 and spot 35sx, pull tubing to 871 and spot 35sx, pull tubing to 280 and circulate cement to surface. 60/40 4% jel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: KBW Oil & Gas Company


STATE OF Kansas COUNTY OF Barber, ss.

Alan Vratil (Employee of Operator or (Operator

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and circumstances of the above statements, and matters herein contained and the log of the above-described well as filed with the State Corporation Commission. The same are true and correct, so help me God.

(Signature) [Signature]

(Address) Medicine Lodge, KS 67104



SUBSCRIBED AND SWORN TO before me this 7 day of March, 1997

[Signature]
Notary Public

My Commission Expires: 10/14/98

RECEIVED
KANSAS CORP COM
MAR 11 P 12:10
3-11-97