

15-007-00671-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 8 Twp. 31S Rge. 14W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE NE NE  
Lease Owner Time Petroleum Company  
Lease Name Don Skinner Well No. 1  
Office Address 815 Union National Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 4-1-64 19  
Application for plugging filed 4-1-64 19  
Application for plugging approved 4-1-64 19  
Plugging commenced 4-1-64 19  
Plugging completed 4-1-64 19  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4634 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	281'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 275' bridge, Plug, 25 sacks cement  
Mud to 40' bridge plug & 10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION

APR 7 1964  
4-7-64

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address P. O. Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Leslie Kite

P. O. Box 486, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of April, 1964

My commission expires April 1, 1967

Ulanda Nichols  
Notary Public.

DRILLER'S LOG

COMPANY: Time Petroleum Company  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: DON SKINNER #1  
 LOCATION: SE NE NE Sec. 8-31S-14W  
 BARBER COUNTY, KANSAS  
 COMMENCED: 3-14-64  
 COMPLETED: 4-1-64

0	50	Surface Soil & Sand
50	375	Clay & Shale
375	985	Shale & Redbed
985	1018	Redbed
1018	1400	Shale
1400	1830	Shale & Shells
1830	1980	Shale & Lime
1980	2085	Lime & Shale
2085	2550	Shale & Lime
2550	2910	Lime & Shale
2910	3070	Shale & Lime
3070	3215	Shale, Brown Lime
3215	3340	Shale & Lime
3340	3420	Lime & Shale
3420	3687	Shale & Lime
3687	3804	Lime & Shale
3804	3850	Lime
3850	4044	Lime & Shale
4044	4400	Lime
4400	4495	Lime & Chert
4495	4520	Shale & Sand
4520	4542	Shale & Lime
4542	4559	Lime
4559	4585	Shale & Lime
4585	4602	Lime & Shale
4602	4634	Lime
	4634	<u>Rotary Total Depth</u> - D. & A.

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 7 1964  
 4-7-64  
 CONSERVATION DIVISION  
 Wichita, Kansas

Viola Top 4400  
 Simpson Top 4484  
 Arbuckle Top 4608

Set 8 5/8" used surface casing @ 281' with landing joint cemented with 225 sacks Common with 2% Gel 3% c.c.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Don Skinner #1 well, located SE NE NE of Section 8, Township 31 South, Range 14 West, Barber County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite  
 Leslie Kite

STATE OF KANSAS )  
 )§S  
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 6th day of April, 1964.

Ulanda Nichols  
 Ulanda Nichols, Notary Public

My Commission Expires:  
 April 1, 1967