

15-007-01570-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely.
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Barber County, Sec. 8 Twp. Rge. 31 (E) 14 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE NW SE $\frac{1}{4}$

Lease Owner M. B. Armer

Lease Name Skinner Well No. 1

Office Address 306 Insurance Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed February 1949

Application for plugging filed June 1949

Application for plugging approved June 1949

Plugging commenced June 1949

Plugging completed June 27 1949

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Maquoketa Depth to top 4323 Bottom 4352 Total Depth of Well 4352 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				13-3/8"	76'	none
				5 1/2"	4347'	3081'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug back from bottom to 4200' with sand and mudded to 4200' bridge and dumped 5 sacks cement. Pulled 5 1/2" and mudded hole to 75' - dumped 15 sacks cement at 75'. Mudded hole and put 10 sacks of cement at top.

RECEIVED

8-5-49
AUG 5 1949

STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to M. B. Armer
Address 306 Insurance Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

L. C. Sponenberg (employee of owner) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg

306 Insurance Bldg., Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 4th day of August 1949

Notary Public

My commission expires Sept. 17, 1951

22-5133-s 9-48-10M



PLUGGING
FILE SEC 8 T 31 R 14
BOOK PAGE 104 LINE 3

Company: M. B. Armer
 Drilling Contractor: Armer Drilling
 Company, Inc.
 Date commenced: 12/17/48
 Date completed: 2/4/49
 Elevation: 1635 D. F.
 Rotary Rig #2

Farm: Skimer #1
 Location: SE NW SE Sec. 8-31-11,
 Barber County, Kansas
 Casing Record: 76' of 13-3/8"
 5 1/2" set @ 1347' cemented w/200 sacks

(figures below indicate bottoms)

Sand and gravel	70
Shale	77
Red bed	100
Shale-shells	370
Red bed & shells	500
Red bed	513
Anhydrite	560
Shale & red bed	690
Shale, red bed	710
Shale & shells	930
Shale	1030
Salt, shale & shells	1260
Shale & shells	1575
Shale & lime shells	1680
Lime	1705
Shale & lime	1805
Lime	1950
Lime, shale	2000
Lime	2025
Lime & shale	2125
Lime & sharp sand	2185
Lime	2375
Shale, lime	2510
Broken lime	2580
Lime & shale	3680
Lime	3712
Lime & sand	3729
Sand	3752
Shale, sand	3760
Sandy shale & lime	3800
Lime	3870
Lime & junk	3923
Lime	4057
Lime, cherty	4090
Lime	4104
Cherty lime	4130
Lime	4170
Lime & shale	4216
Lime	4265
Lime chert	4270
Lime & shale	4312
Lime	4315
Total Depth - correction	4352
(strapped drill pipe out of hole)	
T.P.S. (corrected) Rotary Bushing Meas.	
Lansing	3752
Maquoketa	4323

1635
 2688

RECEIVED

AUG 5 - 1949

STATE CORPORATION
 COMMISSION
 KANSAS

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARMER DRILLING COMPANY, INC.

By L. C. Armer

Subscribed and sworn to before me, a notary public, in and for said County and State this 9th day of February, 1949.

Walter
 Notary Public.

My commission expires Sept. 17, 1951

PLUGGING
 FILE SEC 8 T 31 R 14 W
 BOOK PAGE 104 LINE 3