

15-007-20225-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas
P.O. Box 17027
67217

Barber County, Sec. 8 Twp. 31S Rge. 14 (X) (W)

Location as "NE/CNW/SW" or footage from lines NW NE SE

Lease Owner Kedco Corporation

Lease Name Mills "B" Well No. 1

Office Address 816 Union Center Bldg., Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 30 19 73

Application for plugging filed January 30 19 73

Application for plugging approved January 30 19 73

Plugging commenced January 30 19 73

Plugging completed January 30 19 73

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein, Attica, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4480 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	740'	8 5/8"	740'	None
		Set 40'	of 16"	Conductor	w/100 sacks cement	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug: 500' w/40 sacks cement
40' w/15 sacks cement
2 sacks cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION
FEB 9 1973
2-9-73
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hellar Drilling Company, Inc.

Address 339 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.

D. L. Hellar, President of Hellar Drlg. Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. L. Hellar, President


339 Union Center Bldg., Wichita, Kansas 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of February, 1973

Catherine Darcey
Catherine Darcey Notary Public.

My commission expires March 25, 1976.



DRILLER'S LOG

COMPANY: Kedco Corporation, 816 Union Center Bldg., Wichita, Kansas 67202
 CONTRACTOR: Hellar Drilling Company, Inc., Wichita, Kansas 67202
 LEASE: #1 Mills "B"
 COMMENCED: January 16, 1973
 COMPLETED: January 30, 1973
 CASING: Set 40' of 16" Conductor w/100 sacks cement
 Set 8 5/8" Surface Casing @ 740' w/200 sacks cement

0-50	Soil & surface sand
50-440	Red Bed & Sand
440-742	Shale & Sand
742-1428	Shale & Red Bed
1428-1825	Shale & Anhydrite Streaks
1825-2163	Shale & Anhydrite
2163-2390	Lime & Shale
2390-2630	Lime & Shale (Ft. Riley)
2630-3545	Lime & Shale
3545-3635	Lime & Shale (Toronto)
3635-3735	Lime
3735-3888	Lime & Shale
3888-4040	Lime & Shale (L.K.C.)
4040-4132	Lime
4132-4282	Lime w/Shale Streaks
4282-4398	Viola
4398-4470	Lime
4470-4480	Simpson
4480	Rotary Total Depth
	D & A

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 9 1973
 2-9-73
 CONSERVATION DIVISION
 Wichita, Kansas


STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Mills "B", located in NW NE SE 8-31S-14W, Barber County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 7th day of February, 1973.



Catherine Dargey
 Notary Public - Catherine Dargey

My Commission Expires:
 March 25, 1976.