

15-007-10163-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Barber

County, Sec. 8 Twp. 31 Rge. 14 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE SE SE

Lease Owner J. M. Huber & Cities Service

Lease Name Mills Well No. 2

Office Address 916 S. Pine St - Pratt, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 2-21-47 19

Application for plugging filed 1-7-52 19

Application for plugging approved 1-8-52 19

Plugging commenced 1-8-52 19

Plugging completed 1-12-52 19

Reason for abandonment of well or producing formation

Not sufficient production

If a producing well is abandoned, date of last production July 28, 1951 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough - Great Bend, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4370' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				15 1/2"	115'	None
				10 3/4"	800'	None
				5 1/2"	4353'	3206'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set fresh water plug at 275' and cemented w/20 sacks of cement.  
Mudded hole to 35'; set bridge and cemented with 10 sacks.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to J. M. Huber Corporation  
Address Drawer 460  
Pratt, Kansas

STATE OF KANSAS, COUNTY OF PRATT, ss.

I, J. L. Kyler (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of January, 1952

My commission expires September 10, 1955

22-5133-s 9-48-10M

PLUGGING  
FILE SEC 8 T31 R 14  
BOOK PAGE 132 LINE 33

JAN 23 1952  
1-23-52  
Notary Public

COMPANY: Huber & Cities Service LOCATION: NE SE SE  
 CONTRACTOR: J. M. Huber Corp. Sec. 8-31S-14W  
 FARM NAME: Mills #2 Barber County, Kans.

COMMENCED: December 26, 1946 CASING USED: 15½" at 115' w/450 sacks  
 COMPLETED: February 21, 1947 10 3/4" @800' w/300 sacks  
 5½" at 4353' w/125 sacks

<u>Formation:</u>	<u>From</u>	<u>To</u>
Sand, Gravel bed	0	60
Red rock, clay, shell	60	128
Red bed, shells	128	800
Shale, shells	800	1175
Salt, shale, shells	1175	1550
Shale, shells	1550	1710
Lime, shale	1710	3545
Lime	3545	3635
Shale, lime	3635	3690
Sand	3690	3705
Shale, lime	3705	3860
Lime	3860	4135
Lime, shale	4135	4300
Shale	4300	4339
Viola Lime	4339	4346
Lime & shale	4346	4370

Total Depth 4370'

Pipe set at 4353'

JAN 23 1952  
1-23-52