

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 900 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-007-19070-00-01
 API NUMBER N/A
 LEASE NAME Stucky
 WELL NUMBER 2

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

3960 Ft. from S Section Line
3960 Ft. from E Section Line
 SEC. 8 TWP. 31S RGE. 14 (Nor W)
 COUNTY Barber
 Date Well Completed 9-22-81
 Plugging Commenced 2-5-92
 Plugging Completed 2-6-92

LEASE OPERATOR Apollo Energies, Inc
 ADDRESS RR 1 Box 60 Kingman, Ks 67068
 PHONE (316) 532-2390 OPERATORS LICENSE NO. 30481
 Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)
 The plugging proposal was approved on 10-10-91 (date)
 by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? Yes
 Producing Formation Ninnescha Depth to Top 632 Bottom 656 T.D. 671

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Ninnescha</u>	<u>SALT WATER</u>	<u>632</u>	<u>656</u>	<u>7"</u>	<u>671'</u>	<u>0</u>
				<u>10 3/4</u>	<u>682</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from feet to feet each
Tag out packer w/ 2" Tbg @ 550' Pump thru Tbg, 40sk Cant w/ 50# Halls

3% cc **SEE BACK**

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor CLARKE Corp. License No. 5105
 Address 106 W FOWLER Medicine Lodge, Ks. 67104
 NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: APOLLO ENERGIES, INC
 STATE OF KANSAS COUNTY OF KINGMAN, ss. NOV 17 1992

(Employee of Operator) or (Operator)
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and circumstances of the above-described well as filed with the State Corporation Commission and the log of the above-described well as filed with the same are true and correct, so help me God.

(Signature) [Signature]
 (Address) _____

SUBSCRIBED AND SWORN TO before me this 16th day of November, 1992



[Signature]
 Notary Public

My Commission Expires: August 27 1993

2-1992

WED

Feb 5

Stucky #2 SWD

P+H

MIRU Clark & W.S. (MARK Magarstein)
 RIH W 278" Tbg, Tag old PRR? IN 7"
 565' P.O. + Set Tbg @ 550'; Pumped
 40sx Com. Cmt. Plug w/ 50' Halls - 3% c.c.
 P.O.H w/ 12 Jts, Left 6 Jts in, Let set
 1 Hr, Ran Sals + Tagged Cmt. @ 380' - 440'
 Soft. Landed 12 Jts Tbg @ 368' Pumped
 100sx 60/40 Poz 6% Gel Down Tbg TO Plug T' Csg.
 circ. then went on Vac, Pumped 4 sx down
 Annulus held 500# PSI. Let set 2 1/2 Hrs.
 Pumped 20 sx circ good, then went back on Vac.
 Pumped 100# hulls w/wtr circ good, Pumped
 80 sx 60/40 Poz + circ good Then lost circ
 Again SD. O.N.

THRU

Feb 6

Stucky #2 SWD

RIH W/Tbg Tag soft Cement @ 130' Hrd
 Cmt. @ 150' Pumped 25 sx Common Cmt 3% c.c
 Circ good. Thru 4 Jts Tbg @ 124', P.O.H.
 Cement settled to 12' From surface + Stayed