

15-007-01740-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

BARBER County, Sec. 18 Twp. 31 Rge. 14 (E) W (W)  
NW, SW, SE

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW&SW&" or footage from lines \_\_\_\_\_  
Lease Owner W. J. Coppinger  
Lease Name Shaft Well No. 1  
Office Address 320 Union Natl. Bldg. Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed April 19, 19 57  
Application for plugging filed April 19, 19 57  
Application for plugging approved April 19, 19 57  
Plugging commenced April 19, 19 57  
Plugging completed April 19, 19 57  
Reason for abandonment of well or producing formation No productable zone

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4627' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	@ 830'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mixed heavy mud, filled hole, pushed 1st plug to 300' topped with 1/3 sx. hulls and 20 sx. cement through drill pipe. Mixed heavy mud, filled hole, pushed 2nd plug to 30' topped with 1/3 sx. hulls and 10 sx. cement to base of well cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY  
Address R. R. #2 Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Verne A. Morris (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 3 - 1957  
CONSERVATION DIVISION  
Wichita, Kansas

(Signature) Verne A. Morris  
R.R. #2 Great Bend Kans. (Address)

SUBSCRIBED AND SWORN to before me this 1st day of May, 19 57

My commission expires November 12, 1958

Grandfuchung Notary Public.

24-7368-S 3-53-20M

PLUGGING  
FILE SEC. 18 T. 31 R. 14 W  
BOOK PAGE 7 LINE 38

15-007-01740 0000  
WELL LOG

COMPANY W. J. COPPINGER

SEC. 18 T. 31S R. 14W

FARM SHAFT

NO. 1

LOC. NW, SW, SE


TOTAL DEPTH 4627'

COUNTY Barber Co., Kansas

COMM. April 1, 1957

COMP. April 19, 1957

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 830' W/600 sax.

ELEVATION 1757' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

165	Surface soil & clay	Heebner	3700
250	Shale	Toronto	3739
660	Red bed, shale & shells	Douglas	3762
740	Red Bed & shells	B. Lime	3861
766	Anhydrite	Lansing	3876
830	Red bed & shale		
1800	Shale & shells		
1820	Salt		
1945	Lime & shale		
2255	Lime		
2295	Lime & shale		
2390	Lime		
3575	Lime & shale		
3744	Lime		
3844	Lime, shale & sand		
3861	Lime & shale		
4429	Lime		
4445	Chert & lime		
4490	Conglomerate		
4595	Lime & chert		
4627	Chert, sand & lime		
4627	T. D.		

RECEIVED  
STATE CORPORATION COMMISSION

MAY 3 1957  
5-3-57  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 18 T. 31 R. 14W  
BOOK PAGE 7 LINE 38

State of KANSAS

County of BARTON

ss:

I, Verne A. Morris of Garvey Drilling Co.

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Shaft well

*Verne A. Morris*

Subscribed and sworn to before me this 1st day of May 19 57

My Commission Expires November 12, 1958

*Brantley*  
NOTARY PUBLIC