

15-007-00266-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barber County, Sec. 18 Twp. 31S Rge. (E) 14 (W)

Location as "NE/CNW/SW" or footage from lines Ctr. NE/4 NW/4 NW/4

Lease Owner Monsanto Chemical Company (Lion Oil Company Division)

Lease Name Shaft Well No. 1

Office Address P. O. Box 580; Pratt, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 9, 19 56

Application for plugging filed August 9, 19 56

Application for plugging approved (Verbal) August 9, 19 56

Plugging commenced August 9, 19 56

Plugging completed August 9, 19 56

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Merle Rives

Producing formation None Depth to top Bottom Total Depth of Well 4715' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	814.16'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 4715' to 300'. Set plug at 300' with 20 sacks cement on top of plug. Fill with heavy mud to 40'. Set plug with 1/4 sack hulls and 10 sacks cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Company Inc.

Address 420 W. Douglas; Wichita, Kansas

STATE OF Kansas, COUNTY OF Pratt, ss. W. H. Price (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. H. Price

P. O. Box 580; Pratt, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 10 th day of August, 19 56


My commission expires September 19, 1959

Notary Public

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1956
8-13-56
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 18 T 31 R 14W
BOOK PAGE 89 LINE 29



Sierra Petroleum Co., Inc.
SHAFT #1

NE NW NW Sec. 18-31S-14W
Barber County, Kansas

Total Depth: 4715'

Elev: 1661 KB

Comm: 7/19/56

Comp: 8/9/56

Casing:

Cement

8 5/8 @ 823'

500 sacks of Pozmix

FORMATION	DEPTH
Sand & redbed	100
Red Bed	180
Shale	500
Sand	540
Shale & shellks	825
Shale	1020
Anhydrite	1060
Shale & shells	1740
Shale & lime	1925
Lime	2050
Lime & shale	2745
Shale & sand	2928
Shale & lime	3343
Lime	3467
Lime & shale	3590
Lime	3669
Lime & shale	3824
Lime	4240
Lime & shale	4280
Lime	4311
Lime & shale	4360
Lime	4423
Shale & lime	4445
Lime	4554
Lime & shale	4570
Sand	4580
Sand & chert	4592
Sand	4610
Sand & shale	4672
Lime	4715

Tops:	DEPTH
Anhydrite	1040
Topeka	3203
Heebner	3634
Toronto	3651
Dayton	3677
Lansing K. C.	3809
Base K. C.	4160
Mississippi	4243
Viola	4437
Simpson	4558
Arbuckle	4673

PLUGGING
 FILE SEC 18 T 31 R 14W
 BOOK PAGE 89 LINE 29

RECEIVED
 STATE CORPORATION COMMISSION

AUG 14 1956
 8-14-56
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss:
 COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. T. Honaker

Subscribed and sworn to before me this 13th day of August, 1956.

Margie Cooper
 Notary Public