


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 31 Twp. 33S Rge. 12W (E) (W)  
Location as "NE/CNW&SW" or footage from lines NE NW NE  
Lease Owner Rupp-Ferguson Oil Co.  
Lease Name Hall Well No. 1  
Office Address 523 Petroleum Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 28, 1954  
Application for plugging filed November 28, 1954  
Application for plugging approved November 28, (verbally) 1954  
Plugging commenced November 28, 1954  
Plugging completed November 28, 1954  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5103 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8"	310'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set bottom plug at 300' with 25 sacks cement.  
Top plug at 30' with 15 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rupp-Ferguson Oil Co.  
Address 523 Petroleum Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
L. W. Knox (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. W. Knox  
L. W. Knox, Landman  
523 Petroleum Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of December, 1954

My commission expires January 16, 1957

Katherine E. Allan  
Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 9 - 1954

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE DEC 31 T 33S 12W  
BOOK PAGE 10 LINE 36

CONTRACTOR'S WELL LOG

COMPANY	Rupp-Ferguson Oil Co.
CONTRACTOR	Rupp-Ferguson Oil Co.
FARM	Hall #1
LOCATION	NE NW NE Sec. 31-33S-12W Barber County, Kansas
COMMENCED	November 8, 1954
COMPLETED	November 28, 1954

0	35	Surface soil and clay		
35	92	Silt		
92	105	Sand & gravel		
105	120	Shale & shells		
120	670	Red bed		
670	680	Anhydrite		
680	1200	Shale & shells		
1200	1430	Salt & shale streaked		
1430	1610	Shale & shells		
1610	2600	Lime & shale		
2600	2795	Shale & shells		
2795	2925	Shale & lime		
2925	3065	Shale		
3065	3995	Lime & shale		
3995	4111	Lime		
4111	4165	Lime & shale		
4165	4306	Lime		
4306	4366	Lime, shale streaks		
4366	4426	Lime & shale		
4426	4472	Lime		
4472	4521	Lime & shale		
4521	4524	Chert & lime		
4524	4748	Shale & cherty lime		
4748	4800	Shale	Heebner	3700 (-2212)
4800	4900	Viola	Douglas	3794 (-2306)
4900	4910	Sand	Lans.-K.C.	3874 (-2386)
4910	4948	Simpson	Miss. Chert	4509 (-3021)
4948	4963	Sand	Kinderhook	4687 (-3199)
4963	5001	Sand & shale	Viola	4799 (-3311)
5001	5029	Shale	Simp. Sh.	4901 (-3413)
5029	5077	Sand & shale	Simp. Sd.	4905 (-3417)
5077	5103	Arbuckle	Arbuckle	5069 (-3581)
	5103	Rotary Total Depth	R.T.D.	5103 (-3615)

Set 13 3/8" surface casing at 310' with 350 sacks cement, 200# C.C.

Dry and Abandoned

STATE OF KANSAS        )  
                                  )   SS  
COUNTY OF SEDGWICK )

I, KENNETH RUPP, Partner in Rupp-Ferguson Oil Co., do hereby certify that the above and foregoing is a true and correct copy of the log of the Hall #1, NE NW NE Section 31-33S-12W, Barber County, Kansas as reflected by the files of Rupp-Ferguson Oil Co.

Kenneth Rupp  
Partner

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 8th day of December, 1954.

Katherine E. Allan  
Notary Public

My commission expires January 16, 1957.

**PLUGGING**  
WELL SEC 31-33-12W  
EQUI PAC 10 LINE 36

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 24 1954  
CONSERVATION DIVISION  
Wichita, Kansas