


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County. Sec. 18 Twp. 33S Rge. 15W E#AW
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines W/2-NW NW

Lease Owner Kansas Oil & Gas Partners
Lease Name Brass Well No. 1
Office Address Glenbrook Centre-West, 1140N.W.63rdSt., OK
Character of Well (Completed as Oil, Gas or Dry Hole) City, O
Dry Hole 73116
Date Well completed November 28, 1978
Application for plugging filed Verbal Application 1978
Application for plugging approved Verbal Approval 1978
Plugging commenced November 28, 1978
Plugging completed November 28, 1978
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production 1978

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,806'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	365'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,806 ft. (rotary total depth) to 360 ft. Set plug at 360 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 360 ft. to 40ft. Set solid plug at 40 ft. and cemented to cellar with 12 sacks cement, 3 sacks cement in rat hole.

Plugging operations accomplished utilizing Allied Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co., Inc.
Box 31, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent ~~XXXXXXXXXXXXXXXXXXXX~~ of owner ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 N. Main, Wichita, Kansas 67202
(Address)



SUBSCRIBED AND SWORN TO before me this 12th day of December, 1978

RECEIVED
STATE CORPORATION COMMISSION
Elsie Willison
Notary Public.
DEC 13 1978

My commission expires July 25, 1982

CONSERVATION DIVISION
Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY Kansas Oil & Gas Partners
c/o Mr. Roy D. McAninch
FARM Brass NO. 1

SEC. 18 T. 33S. 15W
LOC W/2-NW NW

COUNTY Barber

ROTARY TOTAL DEPTH 4,806'
COMM. November 18, 1978 COMP. November 29, 1978
CONTRACTOR H-30, Inc. (Rig #3)
ISSUED December 12, 1978

CASING

10 3/4"
8 5/8" Set at 365' cemented w/250 exs cement
5 1/2"
4 1/2"

ELEVATION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	80'
Red Bed and Shale	1,000'
Shale	1,715'
Shale and Lime	2,550'
Lime and Shale	2,785'
Shale and Lime	3,020'
Lime and Shale	4,712'
Shale and Lime	4,781'
Lime and Shale	4,806'
Rotary Total Depth	4,806'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

RECEIVED
STATE CORPORATION COMMISSION
DEC 13 1978
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Sedgwick } SS:

Subscribed and Sworn to before me a Notary Public
in and for said county and state this 12th day of
December, 1978.

WILLIAMS
NOTARY PUBLIC

Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
July 25, 1982