


15-007-20090-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above Section Plat

Barber County, Sec. 18 Twp. 31 Rge. 14 (E) (W)
Location as "NE/CNWSW" or footage from lines 50' E of C N/2
Lease Owner Raymond Oil Co., Inc.
Lease Name Shaft #2 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 10
Application for plugging filed 10
Application for plugging approved 10
Plugging commenced 11/8/73 10
Plugging completed 11/10/73 10
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 10
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes Biberstein

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3944 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	200	none
				5 1/2"	3940	1930'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, ran sand to 3700' and ran 5 sacks cement.
Loaded hole, shot pipe at 2513', 2420', pulled pipe. (pipe parted) Bailed hole to 200', set 15' rock bridge and dumped 7 yards ready mix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

NOV 19 1973

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS


STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
CHASE, KANSAS (Address)

Subscribed and Sworn to before me this 12th day of November, 1973

[Signature]
Notary Public.

My commission expires



MAY 17 1959

ORIGINAL

DRILLER'S LOG

COMPANY	Tilco, et al
CONTRACTOR	LEBEN DRILLING, INC.
FARM	SHAFT #2
LOCATION	50' E - C N $\frac{1}{2}$ Section 18-31S-14W BARBER COUNTY, KANSAS
COMMENCED	2-13-69
COMPLETED	2-22-69

Sp. No. 900:1672' KB

0	100
100	435
435	1125
1125	1690
1690	3085
3085	3320
3320	3495
3495	3710
3710	3805
3805	<u>3945</u>
	<u>3944</u>

Red Bed, Sand
 Red Bed
 Shale
 Shale, Shells
 Lime, Shale
 Lime
 Lime, Shale
 Shale, Lime
 Lime
 Lime
RTD

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 24 1973
 10-24-73
 CONSERVATION DIVISION
 Wichita, Kansas

13" 50# used surface casing set @ 200' cemented with 225 sacks Sunset cement, 2% Gel

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Shaft #2 Well, located 50' E - C N $\frac{1}{2}$ of Section 18, Township 31 South, Range 14 West, Barber County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 25th day of February, 1969.

Ulanda Nichols

Ulanda Nichols

My Commission Expires:
April 1, 1971