


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 18 Twp. 31S Rge. 14 (W)
Location as "NE/CNW/SW" or footage from lines 100'S & 10'E of NW NE SW
Lease Owner Brooks Hall
Lease Name Shaft Well No. 1-B
Office Address 1710 Liberty Bank Bldg. Oklahoma City, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 30 19 66
Application for plugging filed January 30 19 66
Application for plugging approved January 30 19 66
Plugging commenced January 30 19 66
Plugging completed January 30 19 66
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Depth to top Bottom Total Depth of Well 4754 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heeb.	3725 -1968			8-5/8"	904'	
Lans.	3900 -2143					
Miss.	4443 -2686					
Kind.	4463 -2706					
Viola	4490 -2733					
Simp.	4617 -2860					
Arb.	4740 -2983					
TD	4754 -2997					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 300' Wood plug and 25 sxs. Cement.
Mud to 40' Wood plug 1/2 sx Halls and 10 sxs. Cement

RECEIVED
STATE CORPORATION COMMISSION

FEB 1 1966
2-4-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF KANSAS, COUNTY OF BARTON, ss.
Jack M. Dunham (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 783, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of February, 19 66

My commission expires January 24, 1968

Dorothy Tully

Notary Public.

D R I L L E R S L O G

Shaft #1-B

CASING RECORD:
Ran 28 Jts. 904' 8-5/8"

COMPANY: Brooks Hall

DESCRIPTION: 100'S & 10' P
of NW NE SWTOTAL DEPTH:
4754'CONTRACTOR: Aspen Drilling Co. Sec. 18-T31S-R12W
Barber Co., Kansas

COMMENCED: January 12, 1966

ELEVATION: 1757 K.B.
1754 D.F.
1752 G.L.

COMPLETED: January 30, 1966

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Sand & Shale	0	40	Spudded at 2:15 P.M. 1-12-66.
Clay & Gyp Rock	40	100	Ran 28 Jts. 904' 8-5/8" casing.
Red Rock, Shale & Shells	100	600	Cement bottom w/225 sacks Sunset.
Shale & Shells	600	835	
Shale	835	915	<u>DST #1</u> 4332'-4370'
Shale & Shells	915	1045	Open 1/4 hr. ISI 1/2 hr. open 1 hr.
Shale	1045	1597	FSI 1/2 hr. Fair to good blow
Shale & Shells	1597	1787	in 15 min. Weak and dead in 20
Anhydrite	1787	1823	min. Rec. 30' mud. ISI 38#
Shale & Shells	1823	1845	IFP 38# FSI 38# FF 38#
Shale & Lime Shells	1845	2015	
Shale & Lime	2015	2115	<u>DST #2</u> 4617'-4629'
Lime	2115	2230	Strong blow throughout. Rec.
Lime & Shale	2230	2930	1230 SW w/oil specks. ISI 1478#
Shale & Lime	2930	3075	IF 220# FF 558# FSI 1429#
Lime & Shale	3075	3173	
Lime	3173	3446	Gamma Ray-Neutron Log
Shale & Lime	3446	3555	
Lime & Shale	3555	3840	RTD 4754' D & A
Lime & Sand	3840	3907	
Lime	3907	4527	
Lime Chert	4527	4629	
Sand	4629	4648	
Shale & Sand	4648	4680	
Shale & Lime	4680	4754	

Sample Tops


Heebner	3725	-1968
Lansing	3900	-2143
Mississippian	4443	-2686
Kinderhook	4463	-2706
Viola	4490	-2733
Simpson	4617	-2860
Arbuckle	4740	-2983
TD	4754	-2997

STATE OF KANSAS

SS

COUNTY OF BARTON

The undersigned, being duly sworn on oath, states that the above statement and log are true and a correct record and log of the well drilled at the location above described.


Jack M. Dunham, Tool Pusher

RECEIVED
STATE CORPORATION COMMISSION
FEB 4 1966
2-4-66
CONSERVATION DIVISION
Wichita, Kansas