


15-007-10186-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 17 Twp. 31 Rge. 14 (E) W (W)

Location as "NE/CNW&SW&" or footage from lines. NW SW NE  
Lease Owner Leslie Oil Company  
Lease Name Skinner Well No. A-4  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 5-26-60 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 6-1-60 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4402 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	810'	None
				5-1/2"	4392'	3437'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 4402' and found it open;  
Filled with sand to 4375' and dumped 5  
sacks of cement with dump bailer. Mudded  
hole to 310', set rock bridge to 300',  
dumped 20 sacks of cement and mudded hole  
to 40'. Set 10' rock bridge to 30' and  
dumped 10 sacks of cement to base of celler.

PLUGGING COMPLETED.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 5 1960  
7-5-60  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Knight Casing Pulling Company  
Address Chase, Kansas

STATE OF Kansas COUNTY OF Rice, ss.  
I, Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of June, 1960

My commission expires \_\_\_\_\_  
Thomas V. Dwyer Notary Public.

15-007-10186-000  
DRILLER'S LOG

COMPANY: BISHOP & HUBER  
 CONTRACTOR: BISHOP OIL COMPANY  
 WELL NAME: NO. 4 SKINNER "A"

LOCATION: NW SW NE, 17-31S-14W  
 Barber County, Kansas

COMMENCED: 8-20-48  
 COMPLETED:

ELEVATION: 1650  
 PRODUCTION: Physical potential 345 barrels oil  
 per day plus 5 1/2 water.

CASING USED: 8" at 510'  
 5 1/2" at 4392' with 150 sacks.

Sand	40
Sand & Shale	193
Sand & Red Bed	514
Red Bed	760
Anhydrite & Sand	825
Anhydrite & Shale	1025
Shale & Shells	1313
Gyp & Shale	1515
Shale, gyp and shells	1760
Shale & Gyp	1850
Shale & Lime	1890
Lime & Shale	2090
Lime	2166
Lime & Sand	2217
Lime	2305
Lime & Shale	2360
Lime	2433
Lime & Shale	2691
Shale & Lime	2709
Shale Sandy	2825
Lime & Shale	3070
Lime, shale and sand	3170
Lime & Shale	3232
Shale	3255
Lime	3290
Shale	3315
Lime	3380
Lime & Shale	3520
Lime	3560
Lime & Shale	3620
Shale & Lime	3703
Lime & Shale	3755
Lime	3795
Lime & Shale	3836
K. C. Lime	3880
Lime	4040
Lime & Shale	4078
Lime	4128
Lime & Shale	4167
Lime	4400
Rotary Total Depth	4402

SAMPLE TOPS:

Viola 4371

Drilled cement and cleaned out to rotary total depth 4400'. Filled up with 600' oil in hole. Ran Lane Wells Log. Lane Wells Log showed Top Viola 4377 and 4407 total depth. Drilled deeper to total depth 4402'. Filled up with 1200' oil in hole. Swabbed 91 barrels oil and 19 barrels water/7 hours. Swabbed 32 barrels oil and 2.5 barrels water/3 hours. Treated with 1000 gallons acid through tubing. Pressure built up to 450%. Swabbed 20-25 barrels fluid per hour with a trace of water. Pumped 72 barrels oil/4 hours and 132 barrels oil/5 1/2 hours. Physical Potential 345 barrels oil per day plus 5 1/2 water.  
 COMPLETEN.

STATE CORPORATION COMMISSION  
 MAY 20 1960  
 5-20-60  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 COUNTY OF SEDGWICK ) ss

6. I, Edward A. Huffman, hereby certify that the above is a true and correct copy of the log on the No. 4 Skinner "A", located in the Northwest Quarter of the Southwest Quarter of the Northeast Quarter (NW SW NE) of Section Seventeen (17), Township Thirty-one (31) South, Range Fourteen (14) West, Barber County, Kansas

*Edward A. Huffman*  
 Edward A. Huffman, District Manager  
 J. H. HUBER CORPORATION

Subscribed and sworn to before me this 20 day of July, 1949.

*Sarah A. Rice*  
 Notary Public