


15-007-10177-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barber

County. Sec. 16 Twp. 31S Rge. (E) 14(W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines CW/2 SW, NW

Lease Owner Great Bend Pipe & Supply Company

Lease Name Skinner "D" Well No. 1

Office Address Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed 10/31 1946

Application for plugging filed 5-2-51 19

Application for plugging approved 19

Plugging commenced 5-3-51 19

Plugging completed 5-6-51 19

Reason for abandonment of well or producing formation Sealed

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Stough

Producing formation Depth to top Bottom Total Depth of Well 4351 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5-1/2"		3381'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rocked hole from 4375' to 4340' and ran 5 sacks cement. Mudded hole to 260', set 10' rock bridge and ran 20 sacks cement at 250'. Mudded hole to 25' and ran 10 sacks cement on top. Plugging completed.

RECEIVED
STATE CORPORATION COMMISSION
5-19-51
MAY 19 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Great Bend Pipe & Supply Company
Address Box 414 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARBER, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Great Bend Pipe & Supply Co.

(Signature) By R. Quirence
Box 414, Great Bend, Kans
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of May, 1951

My commission expires 3/30/53 Anna Metzger Notary Public.

PLUGGING
FILE SEC. 46-T-31 R 14
BOOK PAGE 81 LINE 14


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - H & T DRILLING CO.
Farm - Skinner No. 1

SEC. 16 T. 31 R. 14 W
CW/2 SW NW

Total Depth. 4380'
Comm. 10-4-46 Comp. 12-22-46
Shot or Treated.
Contractor.
Issued. 7-12-47

County. Barber
KANSAS



Elevation. _____

Production. 9,000,000 Gas.

CASING:

13 3/8" 136' Com.
8 1/4" 850' Com.

Figures Indicate Bottom of Formations.

red bed	40
red bed & sand	90
red bed & sholls	590
shale & shells	1150
limo & shale	1230
shale & shells	1325
gyp & red bed	1435
shale & shells	1550
limo & shale	2025
limo	2090
limo & shale	2430
limo brkn & shalo	2600
limo & shale	3035
limo	3315
limo & shale	3400
limo	3520
limo & shale	3720
shalo sdy	3766
sand & limo	3780
shale	3800
shale & limo	3830
limo	3990
limo sdy	4005
shale & limo	4045
limo hrd	4055
limo	4115
limo & shale	4345
limo	4346
dolomite	4351
limo cherty	4361
limo cherty	4380
Total Depth.	

Tops:
Maquoketa 4347

RECEIVED
CONSERVATION COMMISSION
5-12-51
MAY 12 1951
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC-16 T-31 R-14 W
BOOK PAGE 81 LINE 14

SKINNER #1

Chas. Hulme Drilling Contractor
 Skinner #1 Well SW $\frac{1}{4}$ NW $\frac{1}{4}$
 Section 16-31 S - 14W
 Barber County, Kansas

Date Commenced October 4, 1946
 Date Completed January 16, 1947

Surface Pipe	136' 8 5/8"	150 sax cement
Intermediate Pipe	850' 8"	325 sax cement
Oil String	4348' 6" 5 1/2"	150 sax cement

Driller's Log

0	590	Red Bed & Shells
590	1150	Shale & Shells
1150	1230	Lime & Shale
1230	1275	Shale & Shells
1275	3830	Lime & Shale
3830	3978	Lime
3978	3990	Hard Gray Lime
3990	4005	Sandy Lime
4005	4045	Lime & Shale
4045	4055	Hard Lime
4055	4346	Lime
4346	4351	Dolomite
4351		T.D.

RECEIVED
 STATE REGULATION COMMISSION
 MAY 16 1951
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 SEC. 16 T. 21 R. 14 W.
 BARBER COUNTY, KANSAS