


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barber County, Sec. 11 Twp. 31 Rge. 14 E/W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_  
Lease Owner C N/2 NW/4  
Lease Name Raymond Oil Co., Inc. Well No. \_\_\_\_\_  
Office Address Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above Section Plot

Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 7/7/78 19\_\_\_\_  
Plugging completed 7/11/78 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_  
depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well OWENS Owens  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3107  
Show depth and thickness of all water, oil and gas formations. \_\_\_\_\_ 4498'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	124'	none
				8-5/8"	814'	none
				4-1/2"	3107'	2313'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded to 3050' and set 4 sacks cement. Shot pipe at 2594', 2513', 2429', 2391', 2349', 2308', pulled 56 joints. Set rock bridge at 490' and ran 8 yards ready mix.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor VOTH CASING PULLING  
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
WALTER VOTH (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter Voth  
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of July, 19 78

My commission expires \_\_\_\_\_



Margaret Melcher  
Notary Public.

GABBERT-JONES, INC.  
 WICHITA, KANSAS  
 DRILLERS' WELL LOG

Lake #1-11  
 C N/2 NW Sec 11-31S-14W  
 Barber County, Kansas

Commenced: 4-26-77  
 Completed: 5-10-77

OPERATOR: MALLONEE-MAHONEY, INC.

From	Depth	To	Formation	Remarks
0		554		
554		836	Shells-Shale	
836		1300	Shale-Lime	
1300		1905	Lime-Shale	
1905		2373	Shale-Lime	
2373		3635	Lime-Shale	
3635		3745	Lime	
3745		3856	Lime-Shale	
3856		3948	Lime	
3948		4116	Lime-Shale	Ran 26 jts of 20# 8-5/8" csg set @ 814' cemented w/200 sks Common 3% CC
4116		4350	Lime	PD @ 2:00 p.m. 4-26-77
4350		4475	Lime-Chert	
4475		4498	Lime	
		4498 - TD		
				Ran 26 jts of 20# 8-5/8" csg set @ 814' cemented w/200 sks Common 3% CC
				PD @ 3:30 p.m. 4-27-77
				1" top w/200 sks Posmix 3% CC - 2% Gel
				PD @ 6:00 p.m. 4-27-77
				Ran 76 jts of 10 1/2# 4 1/2" csg set @ 3107' cemented w/175 sks 50/50 Posmix 12# Gilsonite per sack
				PD @ 5:45 a.m. 5-10-77

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK)


I, the undersigned, being duly sworn on oath, state that the above Drillers Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

*James S. Sutton II*  
 JAMES S. SUTTON II

Subscribed and sworn to before me this 24th day of May, 1977.

*Marjorie Hall*  
 MARJORIE HALL-NOTARY PUBLIC



RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 19 1978  
 6-19-78  
 CONSTRUCTION DIVISION  
 Wichita, Kansas