

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barber

County, Sec. 29 Twp. 31S Rge. 14W (E) (W)

Location as "NE/CNWxSWx" or footage from lines. NW NE NW

Lease Owner Tomlinson & Kathol

Lease Name Skinner Well No. 1

Office Address 1125 Wichita Plaza

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed Jan. 15 19 64

Application for plugging filed Jan. 15 1964

Application for plugging approved Jan. 15 1964


Plugging commenced Jan. 15 1964

Plugging completed Jan. 15 19 64

Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Elving

Producing formation None Depth to top Bottom Total Depth of Well 4535 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud was put into the hole from 4535 (total depth) to a depth of 275 feet where the bottom plug was set and cemented with 30 sacks cement. Mud was again put into the hole to a depth of 40 feet where the top plug was set and cemented with 15 sacks cement. The rat hole was plugged with 20 sacks cement. Surface casing was cut off below ground level and the location abandoned.

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1964
1-23-64

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Tomlinson-Kathol
Address 1125 Wichita Plaza, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Richard C. Davis

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
1125 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of January, 1964

[Signature] Notary Public.

My commission expires 1/19/65

DRILLERS LOG
TOMLINSON & KATHOL
1 SKINNER
NW NE NW, SEC. 29-31S-14W

Contractor - Tomlinson & Kathol

Commenced: 12/28/63
Completed: 1/15/64
Elevation: 1746 KB

<u>From</u>	<u>To</u>	<u>Description</u>	<u>Remarks</u>
0	110	Rock - Clay	
110	305	Rock & Shale	
305	433	Shale	305' 10-3/4" Surface Casing
433	765	Shale & Shells	w/175 sacks cement
765	1701	Shale	
1701	1948	Shale - Lime streaks	
1948	2033	Shale & Lime	
2033	2090	Lime	
2090	2465	Lime & Shale	
2465	2485	Shale	
2485	2668	Lime - Shale	
2668	2752	Shale & Lime	
2752	3079	Shale - Lime	
3079	3499	Shale & Lime	
3499	3634	Lime & Shale	
3634	3680	Lime - Shale	
3680	3756	Shale & Lime	
3756	3952	Shale	
3952	4046	Lime & Shale	
4046	4139	Lime	
4139	4190	Shale & Lime	
4190	4304	Lime	
4304	4339	Limestone	
4339	4442	Lime	
4442	4518	Lime - Shale	
4518	4525	Viola	
4525	4535	Lime	
4535		Rotary Total Depth	

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1964
1-23-64
CONSERVATION DIVISION
Wichita, Kansas

I certify to the best of my knowledge and belief, the above represents a true and accurate driller's log record of the captioned well.


Richard C. Davis

STATE OF KANSAS

SS

COUNTY OF SEDGWICK

Subscribed and sworn to before me this 17th day of January, 1964.


Esther Lamone, Notary Public

My Commission Expires: 1/19/65