

15-007-10197-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber

County, Sec. 29 Twp. 31S Rge. 14W (E) (W)

Center W/2 SW NE

T 31S NORTH R 14W

Location as "NE/CNW/SE/SW" or footage from lines

Lease Owner West Supply Co., Inc.

Lease Name H. W. Skinner "B" Well No. 2

Office Address Box 506 - Chase, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil well

Date well completed January 15 1947

Application for plugging filed May 25 1957

Application for plugging approved May 27 1957

Plugging commenced June 6 1957

Plugging completed June 15 1957

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production January 1957

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4592 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13-3/8"	357'	None
				7" OD	4573'	2870'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled the hole with sand from 4592' to 4560' and ran 5 sacks of cement. Pulled casing up to 1600' and circulated the hole with 35 sacks of jell mud. Pulled rest of casing. Mudded the hole to 300', set a 10' rock bridge and ran 30 sacks of cement. Mudded the hole to 20', set a rock bridge and ran 15 sacks of cement to the base of the cellar. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.

Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.

E. E. O'Brien (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. O'Brien

Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of June, 19 57

My commission expires 7-27-58

Thomas V. Duggin Notary Public

PLUGGING  
FILE SEC. 29 T. 31 R. 14W  
BOOK PAGE 15 LINE 30

JUN 19 57  
6-19-57  
CONSERVATION DIVISION  
WICHITA, KANSAS



0	121	Red Bed
121	250	Red Shale
250	525	Red Bed & Shells
525	700	Red Bed
700	860	Red Bed and Shells
860	1048	Red Bed & Shale
1048	1390	Shale and Shells
1390	1695	Salt and Shale
1695	1840	Shale & Anhydrite
1840	1900	Shale & Shells
1900	1935	Lime & Shale
1935	2025	Lime
2025	2340	Lime & Shale
2340	2375	Lime sandy
2375	2494	Shale & Lime
2494	2530	Lime
2530	3095	Shale & Lime
3095	3170	Lime
3170	3325	Shale & Lime
3325	3565	Lime
3565	3605	Shale & Lime
3605	3675	Lime
3675	3715	Shale & Lime
3715	3725	Shale
3725	3815	Lime
3815	3959	Shale & Lime
3959	3965	Sand
3965	3995	Shale & Lime
3995	4235	Lime
4235	4265	Lime Hard
4265	4312	Lime
4312	4333	Lime Brown Hard
4333	4438	Lime
4438	4465	Shale & Lime
4465	4490	Lime
4490	4510	Shale & Lime
4510	4520	Lime
4520	4532	Shale & Lime
4532	4560	Cherty Shale
4560	4579	Lime & Shale
4579	4589	Lime
4589	4592	Lime & Chert
4592		Total Depth

Formation tops as noted from samples  
by G. M. Kridler, Geologist

Douglas Sand Zone	3960-3980
Kansas City - Lan	4005
Kinderhook (Green Sh)	4510
Viola Ls.	4572

Record of cable tool work

4579 T.D. Rotary hole - Halliburton line measurement.  
Note- Drill pipe measured 4581, casing went to 4579'.  
After cement was drilled, tools did not run on anything  
hard until 4584'.

4584 4587 White Cherty lime - little staining and lot of  
Black Shale in samples.  
Halliburton line measurement 4587 1/2'  
75' oil in 50 minutes - increase in gas  
Swabbed 21 bbls oil in 12hrs.

4587 4592 Lime - Chert - Brown med hard - No increase  
4592 Total Depth