

KCC OIL/GAS REGULATORY OFFICE

DATE 5/13/97

OPERATOR McCoy Petroleum Corp. # 5003

NAME 3017 N. Cypress St.

& ADDRESS Wichita, KS 67226-4003

PHONE NO. Steve O'Neill

OPER. 316-636-2737 OTHER _____

New Situation
 Response to Request
 Follow-up

App. LOCATION E/2 NW, SEC 13, T 20 S, R 25 W ^{TX}

LEASE Ring A Well # 1-13

COUNTY Ness API# 15-135-23,994 - 0000

REASON FOR INVESTIGATION: Alternate II cementing completion

PROBLEM: _____

PERSON(S) CONTACTED: _____

FINDINGS: TD @ 4450', Open hole completion, 8 5/8" @ 641' w/325 sx cement, 15 1/2# 5 1/2" at 4441' w/

Port collar at 1656'. Used 250 sx 65/35 Pozmix 6% gel 1/4# floseal. 125 sx cement

Cement did not circulate. Had circulation for about half of mixing, then lost returns.

Ran temperature survey on 5/14/97. Cement was at 990'. Will complete when well is

completed.

5/19/97 Finished cement job that didn't circulate. Cement was at 950', Pumped 125 sx common 3% cc cement and 75 sx 65/35 Pozmix 6% gel down backside. Pressure went from 600-900#. Fell back to 400#, then went back to 900# at the end. Shut in with 500#.

photos taken: _____

ACTION/RECOMMENDATIONS: Alternate II cementing requirements met.

LEASE INSPECTION

COMPLAINT

FIELD REPORT X

RECEIVED
KANSAS CORP. COMM
MAY 21 A. 2:40
5-27-97

Retain 1 copy Joint District Office
Send 1 copy Conservation Division

By Mike Maier
5/13/97
5/19/97