

KCC OIL/GAS REGULATORY OFFICES

Date: 10/15/13

District: 01

Case #: _____

- New Situation
- Response to Request
- Follow-Up

- Lease Inspection
- Complaint
- Field Report

Operator License No: 4767
 Op Name: Ritchie Exploration, Inc.
 Address 1: Box 783188
 Address 2: _____
 City: Wichita
 State: KS Zip Code: 67278 -3188
 Operator Phone #: (316) 691-9500

API Well Number: 15-171-20987-00-00
 Spot: SE-NW-SE Sec 20 Twp 16 S Rng 31 E / W
 1785 (1795) Feet from N / S Line of Section
 1775 (1791) Feet from E / W Line of Section
 GPS: Lat: 38.64761 Long: 100.76771 Date: 10/15/13
 Lease Name: Hell Creek 20D Well #: 1
 County: Scott

Reason for Investigation:

Company requested a state witness to the alternate II cementing job.

Problem:

Alternate II cementing requirements have not been met.

Persons Contacted:

None.

Findings:

8 5/8" surface casing was set @ 210' with 160 sx cement. TD is 4735'. 4 1/2" production casing was set @ 4734' with 225 sx cement on the primary cementing job. Company opened the port collar @ 2327'. Consolidated Oil Well Services, L.L.C. pumped 365 sx cement, circulating 15 sx to the pit. Closed the port collar.

Action/Recommendations:

Follow Up Required Yes No ?

Date: _____

None. Alternate II cementing requirements have been met.

60/40 poz, 6% gel, 1/4# floseal, 500# hulls by Consolidated Oil Well Services, L.L.C.

Verification Sources:

Photos Taken: 0

- RBDMS
- T-I Database
- Other: On-site witness.
- KGS
- District Files
- TA Program
- Courthouse

By: Eric MacLaren
 Eric MacLaren

Retain 1 Copy District Office
Send 1 Copy to Conservation Division

RECEIVED
KANSAS CORPORATION COMMISSION

RECEIVED
 OCT 19 2013
 KCC DODGE CITY

OCT 22 2013
 CONSERVATION DIVISION
 WICHITA, KS

Form: 02/22/2008