

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barber County. Sec. 7 Twp. 33 Rge. 11W (X) (W)

Location as "NE/CNW/SW" or footage from lines C SE SW
Lease Owner K & E Drilling Inc.
Lease Name Fritzgerald Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced May 21, 19 60
Plugging completed May 25, 19 60
Reason for abandonment of well or producing formation Depleted

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4483' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	347'	None
				5-1/2"	4482'	3741'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 4453' and found it open.
Filled with sand to 4400' and dumped 5 sacks
of cement with dump bailer. Pulled 5 1/2" casing.
Cleared hole and set plug @ 300'. Set rock
bridge on plug to 290' and dumped 20 sacks of
cement. Mudded hole to 40; set rock bridge
to 30' and dumped 10 sacks of cement to base
of cellar. Plugging completed.

RECEIVED
STATE CORPORATION COMMISSION

SEP 2 9 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of September, 1962

My commission expires May 20, 1964

Milton J. Volini
Notary Public.





ROTARY DRILLING LOG

OPERATOR: K & E Drilling Company
Fitzgerald #1
E/2 SE SW Sec. 7-33-11W,
Barber County, Kansas

CONTRACTOR: Prime Drilling Company
COMM: 9-30-59
COMP: 10-19-59

Remarks: Set 8-5/8" surface casing
at 355' cemented with 225
sacks Pozmix Quick Set
cement.

Formations:

Surface	30'
Sand & Clay	50'
Shale	356'
Red Bed & Shale	800'
Shale	1020'
Anhydrite	1045'
Shale	1210'
Shale & Shells	1460'
Shale & Lime	1755'
Lime & Shale	1870'
Lime	2080'
Lime & Shale	2405'
Shale & Lime	2955'
Lime & Shale	3120'
Lime	3295'
Lime & Shale	3395'
Shale & Lime	3505'
Lime & Shale	3585'
Shale & Lime	3622'
Sand & Shale	3635'
Shale & Sand	3687'
Shale & Lime	3775'
Lime	4268'
Lime & Shale	4304'
Lime	4483'
Rotary Total Depth	4483'

RECEIVED
STATE CORPORATION COMMISSION
SEP 26 1962
CONSERVATION DIVISION
Wichita, Kansas

Set 5-1/2" casing at 4482' cemented
with 100 sacks Pozmix.

We certify the above log is true and
correct to the best of our knowledge
and belief.

PRIME DRILLING COMPANY

R. R. McNicol
R. R. McNicol