

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-23, 088-00-00

LEASE NAME Circle

WELL NUMBER 1-14

990' Ft. from S Section Line

1650' Ft. from E Section Line

SEC. 14 TWP. 33S RGE. 11W (E) or (W)

COUNTY Barber

Date Well Completed 12/14/85

Plugging Commenced 8-24-87

Plugging Completed 8-28-87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Boswell Energy Corp.

ADDRESS 6001 N. Robinson, Oklahoma City, OK 73118

PHONE#(405) 840 4073 OPERATORS LICENSE NO. 4538

Character of Well Oil-Gas

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation Mississippian Depth to Top 4505 Bottom 4525 T.D. 4625'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	260'	None
				4 1/2	4625'	3401.68'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
A 40 sack bottom hole plug was pumped to 4088'. Pipe was shot free @ 3425'.  
A 50 sack plug was pumped @ 600'. Pumped a 40 sack plug from 320' to 220'.  
Finished pulling pipe. Surface was capped with a 10 sack plug from 40' to 3'.  
Welded on a steel plate.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wilson Casing Pulling, Inc. License No. 03158

Address P.O. Box 963, Woodward, Oklahoma 73802

STATE OF Oklahoma COUNTY OF Woodward, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Jack C. Nelson VICE PRESIDENT

(Address) 6001 N ROBINSON, OKLA CITY, OK 73118


SUBSCRIBED AND SWORN TO before me this 10th day of September, 19 87

Janice K. Boyd  
Notary Public

My Commission Expires: 2-20-89



DUAL INDUCTION/SFL W/GR



COMPANY: BOSWELL ENERGY CORPORATION

WELL: CIRCLE #1-14

FIELD: WILDCAT

*ENGR. COPY*

COUNTY: BARBER

STATE: KANSAS

NATION: USA

LOCATION: 1650' FEL & 990' FSL

SEC: 14

TWP: 33S

RGE: 11E

PERMANENT DATUM: G.L.

ELEVATIONS-

ELEV. OF PERM. DATUM: 1485.0 F

KB: 1485.0

LOG MEASURED FROM: K.B.

DF: 1488.0

5.0 F ABOVE PERM. DATUM

GL: 1490.0

DRLG. MEASURED FROM: K.B.

DATE: 21 NOV 85

RUN NO: 1

DEPTH-DRILLER: 4625.0 F

*Final Print*

DEPTH-LOGGER: 4625.0 F

BTM. LOG INTERVAL: 4619.0 F

TOP LOG INTERVAL: 260.0 F

CASING-DRILLER: 261 F

CASING-LOGGER: 260 F

CASING: 8 5/8"

WEIGHT: 24.00 LB/F

BIT SIZE: 7 7/8"

DEPTH: 4635 F