

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

C SW SW
COUNTY Barber SEC. 14 TWP. 33S RGE. 11 E/W
Location as in quarters or footage from lines:

Lease Owner Eagle Explorations, Inc.
Lease Name Circle Well No. 1
Office Address 107 N. Market Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed 12-5-81
Application for plugging filed Jan. 4, 1983
Plugging commenced Oct. 13, 1983
Plugging completed Oct. 14, 1983
Reason for abandonment of well or producing formation

Locate Well
correctly on above
Section Platt.

Not economical to produce
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation Mississippi Depth to top 4621' bottom 4629' T.D. 5084'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record


Formation	Content	From	To	Size	Put in	Pulled Out
		0	375'	8 5/8"	375'	0'
		1	5086'	5 1/2"	5083'	3516'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Set CIBP at 4600', dumped 5 sx. cement with Welex dump bailer, pulled 3516' 5' casing. Pumped 3 hulls, 10 gel, 1 hull, released 8 5/8" plug and pumped 130 cement, used 60-4- poz mix, 2% gel, 3% calcium chloride. Job completed at 6:30 PM, 1-14-83 by Sun Cementing. Max. pumped 500 psi, shut 400 psi.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pratt Well Service, Inc.

STATE OF Kansas COUNTY OF Pratt, ss.
Judy Berry (employee of owner) or (~~owner~~) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.



(Signature) Judy Berry
Box 847 Pratt, Ks. 67124
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of November, 1983

Charlene M. Ducrey
Notary Public.

My Commission expires: 9/10/86

NOV 28 1983
CONSERVATION DIVISION
Wichita, Kansas

15-007-01155-00-00

COUNTY BARBER
FIELD or WILDCAT
LOCATION SEC. 14-33S-11W
WELL CIRCLE NO. 1
COMPANY EAGLE EXPLORATION

COMPANY EAGLE EXPLORATION

WELL CIRCLE NO. 1

FIELD WILDCAT

COUNTY BARBER STATE KANSAS

API Serial No.
Location: SE/4
Sec. 14 Twp. 33S Rge. 11W

Other Services:
CNL/FDC-GR
PML
DI-SFL

Permanent Datum: GROUND LEVEL; Elev.: 1467
Log Measured From K.B., 14 Ft. Above Perm. Datum
Drilling Measured From K.B.

Elev.: K.B. 1481
D.F.
G.I. 1467

Date	3-20-81		
Run No.	ONE		
Depth-Driller	5105		
Depth-Logger (Schl.)	5103		
Btm. Log Interval	5100		
Top Log Interval	372		
Casing-Driller	8 5/8 @372	@	@
Casing-Logger	372		
Bit Size	7 7/8		
Type Fluid in Hole	PREMIX-MONPAC		
Dens.	9.2	50	
Visc.			
pH	8.5	12 ml	ml
Fluid Loss			
Source of Sample	MUDPIT		
R _m @ Meas. Temp.	.503 @62 °F	.269 @116 °F	°F
R _{mf} @ Meas. Temp.	.290 @75 °F	.188 @116 °F	°F
R _{mc} @ Meas. Temp.	.525 @81 °F	.367 @116 °F	°F
Source: R _{mf} R _{mc}	M C		
R _m @ BHT	.269 @116 °F	@ °F	@ °F
Circulation Stopped	0400		
Logger on Bottom	1330		
Max. Rec. Temp.	116 °F	°F	°F
Equip. Location	7747 WICHITA		
Recorded By	SMITH		
Witnessed By	HELFENBEIN, DILTS		

RECEIVED
JAN 06 1983
CONSERVATION DIVISION
Wichita, Kansas

