

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber County, Sec. 35 Twp. 33S Rge. (E) 11 (W)

Location as "NE/CNW/SW" or footage from lines C NW/4 SE/4

Lease Owner Walters Drilling Co., et al

Lease Name Powell Well No. 1

Office Address 510 Orpheum Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 2, 19 57

Application for plugging filed December 4, 19 57

Application for plugging approved December 4, 19 57

Plugging commenced December 5, 19 57

Plugging completed December 7, 19 57

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Merle Rives, Pratt, Kansas

Producing formation None Depth to top Bottom Total Depth of Well 4620 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None	None	0	230'	8 5/8"	230'	None
Mississippian	None	0	4619 1/2'	4 1/2"	4651'	4150.07'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with gravel to 4388' and dumped 4 sacks cement. Pulled casing to 1800' and circulated with drilling mud and 10 sacks Aquagel. Pulled remainder of casing. Bailed off mud to 235'. Set rock bridge from 235' to 225', mixed and dumped 20 sacks cement, mud to 35', set rock bridge from 35' to 25', mixed and poured 10 sacks cement from 25' to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 20 1957  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Ace Pipe Pulling Co.  
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Robert F. Walters (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert F. Walters  
510 Orpheum Building, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of December, 19 57

My commission expires March 10, 1960 Notary Public.

PLUGGING  
FILE SEC. 35 T. 33 R. 11W  
BOOK PAGE 65 LINE 44

POWELL NO. 1

Location: C NW/4 SE/4 Sec. 35-33S-11W,  
Barber County, Kansas

Date Spudded: 11-1-57

Operator: Walters Drilling Co.

Rotary Completion: 11-16-57

Contractor: Walters Drilling Co.

Elevation: 1417 Gr  
1420 DF  
1422 KB

Surface Casing: 8 5/8" set at 230' with  
175 sacks cement and  
2 Cal. Chloride

Production  
Casing: 4 1/2" set at 4619 1/2' with  
100 sacks cement

L O G

(Figures indicate bottom of formation)

Surface	0 to 230
Shale and Red Bed	300
Shale and Shells	1590
Shale and Lime	3975
Lime	4475
Lime and Shale	4526
Lime	4548
Chert	4620
Rotary Total Depth	4620

RECEIVED  
STATE CORPORATION COMMISSION

JAN 31 1958

CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, Robert F. Walters, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

By

Robert F. Walters

Subscribed and sworn to before me  
this 19th day of November, 1957

Pauline Rudolphson  
Notary Public

My commission expires:  
March 10, 1960

PLUGGING  
FILE SEC 35 T 33 R 11 W  
BOOK PAGE 65 LINE 44