

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-32-3-117

15-007-00361-00-00

API NUMBER D&C 12/07/56

LEASE NAME B.C. FORRESTER "D"

WELL NUMBER 1

990 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 27 TWP. 33S RGE. 11 (E or W)

COUNTY BARBER

Date Well Completed 12/07/56

Plugging Commenced 03/26/86

Plugging Completed 03/28/86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR CHEVRON U.S.A. INC.

ADDRESS P. O. BOX 12116, OKLAHOMA CITY, OK 73157

PHONE# (405) 949-7000 OPERATORS LICENSE NO. 4519

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? DISTRICT #1 DODEG CITY, KANSAS

Is ACO-1 filed? NO RECORDS if not, is well log attached? FILED W/ CP-1

Producing Formation MISSISSIPPI Depth to Top 4504 Bottom - T.D. 4630'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
MISSISSIPPI	GAS, OIL WTR	221	0	8-5/8	221	NONE
		4628	0	5-1/2	4628	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

(SEE BACK OF FORM)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE INC. License No. 5813

Address P. O. BOX 187, PRATT, KANSAS

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

M. O. MCCARTHY

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, I so swear to me God.

STATE CORPORATION COMMISSION

(Signature) Michael O Mc Carthy

(Address) P. O. BOX 12116, OKC, OK 73157

APR 13 1986

SUBSCRIBED AND SWORN TO before me this 11th day of April, 19 86

Wichita, Kansas

Mary Cahemia
Notary Public

My Commission Expires: April 20, 1986

PLUGGING PROCEDURES:

OPERATIONS TO PLUG AND ABANDON FORRESTER "D" #1 BEGAN 03/26/86. MOVED IN AND RIGGED UP PRATT WELL SERVICE INC. RIG #25. RAN IN HOLE W/ PKR ON TUBING TO 3710'. TESTED 5-1/2" CASING TO 500 PSI FOR 10 MINS. OK. CIRCULATED 5-1/2" CASING FULL OF 9 PPG MUD. PULLED OUT OF HOLE W/ RBP AND PKR. RIH W/ CIBP ON WIRELINE. SET SAME AT 4500'. DUMPED 10 SKS "A" CMT ON TOP OF SAME (FROM 4500' TO 4411'.) PERF 5-1/2" CASING AT 660'. RAN IN HOLE W/ CICR ON TBG AND SET AT 600'. ESTABLISHED CIRCULATION DOWN TBG AND TO SURFACE OUT 5-1/2" X 8-5/8" ANNULUS. PUMPED 280 SKS "A" CMT CIRCULATING 25 SKS TO SURFACE OUT 5-1/2" X 8-5/8" ANNULUS. STUNG OUT OF CICR. FILLED 5-1/2" CASING W/ 70 SKS "A" CMT TO SURFACE. PULLED OUT OF HOLE W/ TUBING. CUT OFF CASINGS. CAPPED AND ID WELL. RIGGED DOWN AND MOVED OUT PULLING UNIT. WELL PLUGGED AND ABANDONED 03/28/86.

WITNESSED BY: MR. JACK LUTHI W/ KANSAS CORPORATION COMMISSION

RECEIVED
MARCH 29 1986
0800 A.M.
KANSAS CORPORATION COMMISSION

Barbara Oil Company

Forester "D" # 1

Total Depth

4630'

Comm.

11/18/56

Comp.

12/7/56

Contractor Patton Drilling Co., Inc.

Location NE/4 SW/4 Sec. 27-53S-11W

Barbar County, Kansas.

CASING RECORD

8 5/8" Casing at 221'

Cemented with 165 Sack Cement

5 1/2" Casing at 4629'

Cemented with 250 Sacks Cement

Red Bed & Clay	40
Red Bed	224
Red Bed & Shells	800
Shale, Lime & Salt	1345
Shale & Lime	1720
Lime	2165
Shale & Lime	3005
Lime	3110
Shale & Lime	3715
Sandy Shale & Lime	3810
Shale & Lime	3900
Lime K. C.	3925
Lime	3970
Shale & Lime	4120
Lime	4354
Shale & Lime	4520
Lime Miss.	4550
Lime Cherty	4630
Total Depth	4630

Tops

All Depths from Kelly Bushing 9'

Above ground Level

Top Lansing K. C. 3812'

Top Mississippian 4504'

STATE OF Kansas COUNTY OF Adgwick ss,

I, the undersigned, being duly sworn, on oath state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

PATTON DRILLING COMPANY, INC.

By Robert W. Patton

Subscribed and sworn to before me this 14th day of December 1956.

T. P. Hendrick
Notary Public.
T. P. Hendrick

My Commission Expires Oct 4th 1960.

THE
STATE CORPORATION COMMISSION

MAR 20 1956

CONSERVATION DIVISION
Wichita, Kansas