

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Barber County, Sec. 27 Twp. 33-S Rge. (E) 11 (W)

Location as "NE/CNW/SW" or footage from lines CS/2 NW/4
Lease Owner Barbara Oil Company
Lease Name Forester "C" Well No. 1
Office Address 322 Central Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D&A
Date well completed December 18, 19 58
Application for plugging filed December 18, 19 58
Application for plugging approved December 18, 19 58
Plugging commenced December 18, 19 58
Plugging completed December 18, 19 58
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Lackamp, Jr., Rt. #1, Stafford, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4631 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	211'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud from 4631' to 200', set wood bridge plug at 200' and pumped 20 sacks cement through drill pipe with pump truck, filled up with mud to 35' and set another wood bridge plug with 10 sacks cement on top which filled to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
DEC. 24 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address Fourth National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R.F. Ramsey (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R.F. Ramsey
322 Central Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 19 58

My commission expires March 2, 1961
Mildred Fisher Notary Public.

PLUGGING
FILE SEC. 27 T. 33 R. 11 W
BOOK PAGE a LINE 10

ROTARY DRILLING LOG

COMPANY: Barbara Oil Company
 LOCATION: C-S/2 NW Sec. 27-33S-11W
Barber County, Kansas
Forester "C" #1
 CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

Rotary Drilling Commenced 12-3-58
 Rotary Drilling Completed 12-18-58

CASING RECORD: (8 jts.) 8-5/8" 28# 8thd casing (used) set at 210' with 110 sacks cement. Cement circulated.

(No 5-1/2" casing run. D & A)

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Red Rock	211'
Red Rock & Shale	720'
Shale & Clay	1200'
Shale & Lime	1900'
Lime	2010'
Lime & Shale	2235'
Lime	2330'
Shale & Lime	3025'
Lime	3135'
Lime & Shale	3240'
Lime	3285'
Lime & Shale	3505'
Shale	3620'
Lime & Shale	3696'
Shale, Sand & Lime	3800'
Lime & Shale	4012'
Lime	4095'
Shale & Lime	4167'
Lime	4319'
Lime & Shale	4377'
Lime	4409'
Lime & Shale	4507'
Mississippi	4631' T.D.

Circ. for samples at 4550'
 4580'
 4585'
 4631'

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 10 1959
 CONSERVATION DIVISION
 Wichita, Kansas

S.L.M. at 2000 - O.K.
 3000 - O.K.
 4000 - O.K.

Slope Test at 210 0° off
 500 0° off
 1000 0° off
 1500 1/2° off
 1850 1° off
 2800 1° off
 3000 1° off
 3696 1 1/2° off
 4400 1-3/4° off

PLUGGING
 FILE SEC. 27 T. 33 R. 11W
 BOOK PAGE 9 LINE 10

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts
 Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 29th day of December, 1958, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. SEBITTS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 13, 1962

Mary Ellen Sampson
 Notary Public

(Mary Ellen Sampson)